DIRECTION	MILEPOINT	LOCATION CODE (SHEET 4)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION SIGN DETAIL SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
SB HYDE PARK TH-1							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS BOOK			
SB	2.715	H	R1-1				STOP						1		X											5-10-18			
		H	R1-1	30	30			6.25								1		13.25 X									X		
SB	2.624	EF	D3-1				JEWETT RD						1		X														
		H	R1-1				STOP						1																
		EF	D3-1	42	12			3.50								1		X								MOUNT JEWETT RD PERP ON TOP OF STOP SIGN		10	
		H	R1-1	30	30			6.25																			X		
SB	2.495	F	W1-1R	30	30			6.25								1		15.75 X								INSTALL 240 FT ± NORTH AND ACROSS FROM PROPOSED SIGNS AT MP 2.450	X		
		F	W13-1p	18	18			2.25																			X		
SB	2.295 - 2.167	F	N/A	6	8		INSTALL (9) NEW DELINEATOR POSTS																			WHITE DELINEATORS BACK TO BACK ON 9 NEW POSTS; INSTALL THE FIRST POST AT MP 2.295, 450 FT ± NORTH OF EXISTING UTILITY POLE 34, THEN EVERY 85 FT ±, SEE SHEET 9			
SB	1.758	F	W1-4R				RIGHT REVERSE CURVE						1		X											5-9-18			
		F	W13-1p				30 M.P.H. (PLAQUE)						1																
		F	W1-1R	30	30			6.25								1		15.75 X									X		
		F	W13-1p	18	18			2.25																			X		
SB	1.698	F	VW-133R				HIDDEN DRIVE RIGHT						1		X									9 DEL.					
SIGN SUMMARY SHEET							SHEET TOTALS	33.00	0.00	0	0	0	6	0	0	4		44.75 ~~60.0~~		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	138.8	0.0	1	0	0	20	0	0	24		360.0		0	0.0								

PROJECT NAME: STATEWIDE-NORTH REGION
PROJECT NUMBER: STP HRRR(22)
FILE NAME: z14k100tsshydepark TH1 SB.
PROJECT MANAGER: K. RUTTER
DESIGNED BY: R. SHEDD
HYDE PARK TH-1 SOUTHBOUND 2
PLOT DATE: 5/5/2017
DRAWN BY: R. SHEDD
CHECKED S. GOODWIN
SHEET 122 OF 255