DIRECTION	MILEPOINT	LOCATION CODE (SHEET 4)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION SIGN DETAIL SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
NB HYDE PARK TH-3							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS BOOK			
NB	0.005	A	R1-1				STOP			1				X												5-11-18			
NB	0.007	AB	D3-1				CENTERVILLE RD						1		X														
			D3-1	56	12		Centerville Rd	4.67								2		14.00 X ~~14.25~~										11	
NB	0.007	CD	D3-1				HYDE PARK ROAD						1		X														
			D3-1	68	12		N Hyde Park Rd	5.67								2		14.00 X ~~14.50~~										11	
NB	0.009	C	W1-6				LARGE ARROW LEFT			1				X															
NB	0.151	C	W14-2	30	30		NO OUTLET	6.25								1		14.00 X									INSTALL ON BENSON RD	X	
NB	0.338	D	D3-1				BENSON ROAD						1																
		D	R1-1				STOP						1		X														
		D	D3-1	42	12		Benson Rd	3.50																			MOUNT BENSON RD PERP ON TOP OF STOP SIGN		11	
		D	R1-1	30	30		STOP	6.25								1		13.75 X									REMOVE EXISTING AND INSTALL NEW ONE 10 FT DOWN (AT LOWER MP) ON N. HYDE PARK RD	X	
NB	1.091	A	W1-2L	30	30			6.25								1		14.00 X										X	
NB	2.407	AB	D3-1				McKINSTRY HILL RD						1		X												5-14-18		
		AB	D3-1	68	12		McKinstry Hill Rd	5.67								2		10.00 X ~~10.25~~										11	
SIGN SUMMARY SHEET							SHEET TOTALS	38.25	0.00	2	0	0	5	0	0	9		~~118.75~~ 135.0		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	187.9	0.0	2	2	2	24	0	0	40		600.0		0	0.0								

PROJECT NAME: **STATEWIDE-NORTH REGION**
PROJECT NUMBER: **STP HRRR(22)**

FILE NAME: **z14k100tsshydepark TH3 NB.** PLOT DATE: **5/5/2017**
PROJECT MANAGER: **K. RUTTER** DRAWN BY: **R. SHEDD**
DESIGNED BY: **R. SHEDD** CHECKED **S. GOODWIN**
HYDE PARK TH-3 NORTHBOUND 1 SHEET **125** OF **255**