DIRECTION	MILEPOINT	LOCATION CODE (SHEET 4)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION SIGN DETAIL SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
NB ORANGE TH-1							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS BOOK			
NB	0.009						REMOVE EMPTY POST								X											PAID FOR AS ITEM 676.12, REMOVAL OF EXISTING DELINEATOR, SEE SHEET 8			
NB	0.018	A	VR-017				LLL 24,000 LBS			1				X												6-5-18			
NB	0.034	A	R2-1				SPEED LIMIT 35						1		X														
		A	R2-1	24	30		SPEED LIMIT 35	5.00								1		12.00 X									X		
NB	0.140	A	R2-1				SPEED LIMIT 35						1		X											6-11-18			
NB	0.251	A	R2-1				SPEED LIMIT 35						1		X														
NB	0.265	A	VR-020	24	30		NO PARKING ON TRAVELED LANE	5.00								1		13.50 X								INSTALL 75 FT ± NORTH OF REMOVED SL-35 AT MP 0.251			E-146
NB	0.443	A	R2-1	24	30		SPEED LIMIT 50	5.00								1		12.25 X								INSTALL 15 FT ± SOUTH OF EXISTING SIGN AT MP 0.446	X		
NB	1.500 - 2.009	A		6	8		INSTALL (5) NEW DELINEATOR POSTS																			INSTALL (10) TYPE II 6"x8" WHITE DELINEATORS BACK TO BACK ON 5 NEW POSTS; INSTALL THE POST AT MP 1.500, 370 FT ± NORTH OF EXIST. CABLE BRIDGE RAILING, THEN EVERY 85 FT ±, SEE SHEET 9			
NB	1.945	A	W1-10R	36	36			9.00								2		16.00 X 15.75								6-8-18 INSTALL 70 FT ± NORTH OF UTILITY POLE NET/48 AT MP 1.932	X		
		A	W16-8p	24	8		Lords Rd	1.33																		INSTALL ON LEFT POST		14	
		A	W13-1p	18	18		40 MPH	2.25																		INSTALL ON LEFT POST	X		
NB	2.322	A	R2-5A				REDUCED SPEED AHEAD						1		X														
NB	2.380	A	W3-5	36	36		SPEED LIMIT 35	9.00								2		14.75 X 14.25							5 DEL.	1 DEL. REM.	INSTALL 305 FT ± NORTH OF EXISTING SIGN AT MP 2.322	X		
							SHEET TOTALS	36.58	0.00	1	0	0	4	0	0	7		~~98.50~~ 105.0		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
							TOWN DIRECTIONAL TOTALS	139.8	0.0	1	0	0	17	0	0	27		405.0		0	0.0								

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **STATEWIDE-NORTH REGION**
PROJECT NUMBER: **STP HRRR(22)**

FILE NAME: **z14k100tssorange TH1 NB.xls** PLOT DATE: **5/5/2017**
PROJECT MANAGER: **K. RUTTER** DRAWN BY: **R. SHEDD**
DESIGNED BY: **R. SHEDD** CHECKED **S. GOODWIN**
ORANGE TH-1 NORTHBOUND 1 SHEET **158** OF **255**