DIRECTION	MILEPOINT	LOCATION CODE (SHEET 4)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION SIGN DETAIL SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
NB ORANGE TH-1							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS BOOK			
NB	2.462	A	R2-1				SPEED LIMIT 35						1		X											6-8-18			
		A	R2-1	30	36			7.50								1		13.75 X									X		
NB	2.467	AB	D3-1				GEORGE ST						1		X														
		AB	D3-1	42	12		George St	3.50								1		11.00 X										14	
NB	2.467	C	R2-1				SPEED LIMIT 35						1		X														
		C	R2-1	24	30			5.00								1		12.25 X									INSTALL SIGN IN SAME LOCATION AS EXISTING ON GEORGE ST	X		
NB	2.475	D	R1-1	30	30		STOP	6.25								1		12.25 X									INSTALL ON STOP SIGN SIDE OF GEORGE ST	X		
NB	2.600	A	W2-3L	30	30			6.25								1		14.75 X										X		
		A	W16-8p	24	8		Bisson Rd	1.33																					14	
NB	3.398	A	W2-2R	30	30			6.25								1		14.75 X									6-18-18 INSTALL 290 FT ± SOUTH OF EXISTING SIGN AT MP 3.453	X		
		A	W16-8p	24	8		Griggs Rd	1.33																					14	
NB	3.453	AB	D3-1				GRIGGS RD						1		X														
		AB	D3-1	42	12		Griggs Rd	3.50								1		11.50 X										14	
NB	3.453	C	W14-1	30	30		DEAD END	~~6.25~~				1				1		13.00 X									INSTALL ON GRIGGS RD	X		
SIGN SUMMARY SHEET							SHEET TOTALS	40.92 ~~47.17~~ SF	0.00 SF	0 EA	0 EA	1 ~~0~~ EA	4 EA	0 EA	0 EA	8 EA		103.25 ~~120.0~~ FT			0 EA	0.0 LB	0.0 LB	0.0 LB	0.0 LB				
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	139.8 SF	0.0 SF	1 EA	0 EA	0 EA	17 EA	0 EA	0 EA	27 EA		405.0 FT			0 EA	0.0 LB							

PROJECT NAME: **STATEWIDE-NORTH REGION**
PROJECT NUMBER: **STP HRRR(22)**

FILE NAME: **z14k100tssorange TH1 NB.xls** PLOT DATE: **5/5/2017**
PROJECT MANAGER: **K. RUTTER** DRAWN BY: **R. SHEDD**
DESIGNED BY: **R. SHEDD** CHECKED **S. GOODWIN**
ORANGE TH-1 NORTHBOUND 2 SHEET **159** OF **255**