DIRECTION	MILEPOINT	LOCATION CODE (SHEET 4)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION SIGN DETAIL SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
NB ORANGE TH-1							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																				"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS BOOK			
NB	3.464	C	W14-1				DEAD END				1		1		X											6-8-18 TOWN REQUEST			
		D	R1-1				STOP				1	1	1															
		D	R1-1	30	30		STOP	~~6.25~~								1		12.50 X									X		
NB	3.872	AB	D3-1				TR 12 SMITH ROAD						4		X														
		AB	D3-1	40	12		Smith Rd	3.33								1		11.50 X										14	
NB	3.880	D	R1-1	30	30		STOP	6.25					1			1		13.25 X								INSTALL ON STOP SIGN SIDE OF SMITH RD	X		
NB	3.904	A	R2-1				SPEED LIMIT 35						1		X														
		A	R2-1	24	30		SPEED LIMIT 35	5.00								1		12.00 X									X		
NB	4.063	A	W2-2L	30	30		Cutler Corner Rd	6.25								1		16.50 X								INSTALL 715 FT ± NORTH OF UTILITY POLE 6-8/4 AT MP 3.928	X		
		A	W16-8p	36	8		Cutler Corner Rd	2.00																				14	
NB	4.143						REMOVE EMPTY POST																		1 DEL. REM.	PAID FOR AS ITEM 676.12, REMOVAL OF EXISTING DELINEATOR, SEE SHEET 8			
NB	4.143	C	W1-7	48	24			8.00								2		12.75 X ~~12.75~~								INSTALL IN FRONT OF UTILITY POLE 6/139	X		
NB	4.780	A	S3-2	36	36	FYG	SCHOOL BUS TURN AHEAD	9.00								2		13.25 X 13.75								6-11-18	X		
SIGN SUMMARY SHEET							SHEET TOTALS	~~39.83~~ ~~46.08~~ SF	0.00 SF	0 EA	0 EA	1 ~~0~~ EA	8 ~~7~~ EA	0 EA	0 EA	9 EA		~~118.25~~ ~~135.0~~ FT			0 EA	0.0 LB	0.0 LB	0.0 LB	0.0 LB					
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	139.8	0.0	1	0	0	17	0	0	27		405.0			0	0.0								

PROJECT NAME: **STATEWIDE-NORTH REGION**
PROJECT NUMBER: **STP HRRR(22)**

FILE NAME: **z14k100tssorange TH1 NB.xls** PLOT DATE: **5/5/2017**
PROJECT MANAGER: **K. RUTTER** DRAWN BY: **R. SHEDD**
DESIGNED BY: **R. SHEDD** CHECKED **S. GOODWIN**
ORANGE TH-1 NORTHBOUND 3 SHEET **160** OF **255**