DIRECTION	MILEPOINT	LOCATION CODE (SHEET 4)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION SIGN DETAIL SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
SB ORANGE TH-1							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS BOOK			
SB	2.462	F	R2-1				SPEED LIMIT 50						1		X											6-8-18			
		F	R2-1	24	30			5.00								1		12.75 X									X		
SB	2.040	F	W1-10L	36	36			9.00								2		15.25 X 15.25								INSTALL 250 FT ± NORTH OF EXISTING SIGN AT MP 1.993	X		
		F	W16-8p	24	8			1.33																		INSTALL ON LEFT POST		14	
		F	W13-1p	18	18			2.25																		INSTALL ON LEFT POST	X		
SB	1.993	EF	D3-1				LORDS RD						1		X														
		EF	D3-1	36	12			3.00								1		11.75 X										14	
SB	1.014	EF	D3-1				14 PARTRIDGE RD						~~1~~ 4		X														
		EF	D3-1	52	12			4.33								2		10.25 X 10.25										14	
SB	1.014	G	R2-1	24	30			5.00								1		12.00 X								6-11-18 INSTALL ON PARTRIDGE RD	X		
SB	0.999	H	R1-1				STOP						1		X														
		G	R2-1				SPEED LIMIT 35						1		X														
		H	R1-1	30	30			6.25								1		12.50 X									X		
SB	0.518	F	R2-5A				REDUCED SPEED AHEAD						1		X														
SB	0.518	F	W3-5	36	36			9.00								2		14.00 X 14.50									X		
SIGN SUMMARY SHEET							SHEET TOTALS	45.17	0.00	0	0	0	~~6~~ 9	0	0	10		~~128.50~~ 150.0		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	172.5	0.0	0	1	1	27	0	0	34		510.0		0	0.0								

PROJECT NAME: **STATEWIDE-SOUTH REGION**
PROJECT NUMBER: **STP HRRR(22)**

FILE NAME: **z14k100tssorange TH1 SB.xls** PLOT DATE: **5/5/2017**
PROJECT MANAGER: **K. RUTTER** DRAWN BY: **R. SHEDD**
DESIGNED BY: **R. SHEDD** CHECKED **S. GOODWIN**
ORANGE TH-1 SOUTHBOUND 3 SHEET **164** OF **255**