DIRECTION	MILEPOINT	LOCATION CODE (SHEET 4)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB/FT) 1.88	SQUARE STEEL (IN) 2.00 (LB/FT) 2.42	SQUARE STEEL (IN) 2.50 (LB/FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB/FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB/FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB/FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB/FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION SIGN DETAIL SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
NB ST JOHNSBURY TH-8							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS BOOK			
NB	0.007						~~EMPTY POST~~								~~X~~											~~PAID FOR AS ITEM 676.12, REMOVAL OF EXISTING DELINEATOR, SEE SHEET 7~~			
		CD	D3-1	72	12		Severance Hill Rd	~~6.00~~								~~2~~		~~X~~								INSTALL ON BERLIN-GUILDHALL NHG SIGN(57)		21	
NB	0.045	A	R2-1				SPEED LIMIT 40						1		X											5-22-18			
		A	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS	5.00								1			16.25 X							~~SLIP BASE REQUIRED~~ SEE SHEET 9			T-70
		A	R2-1	24	30		SPEED LIMIT 40	5.00																			X		
NB	0.069	A	VR-017				LLL 24,000 LBS						1		X														
NB	0.304	A	W11-5	30	30			6.25								1		14.50 X								INSTALL 110 FT ± SOUTH AND ACROSS FROM UTILITY POLE 9/10/93/10 AT MP 0.325	X		
NB	0.503	A	W1-4L	30	30			6.25								1		16.50 X								INSTALL ACROSS FROM UTILITY POLE 93/14/14	X		
		A	W13-1p	18	18		30 MPH	2.25																			X		
NB	0.575	A	W1-6	48	24			8.00								2		13.25 X ~~14.00~~								INSTALL 20 FT ± SOUTH OF EXISTING SIGN AT MP 0.579	X		
NB	0.576	B	W1-6	48	24			8.00								2		14.00 X ~~13.25~~									X		
NB	0.579	A	W1-8				LEFT CHEVRON						1		X														
NB	0.600	A	W1-6	48	24			8.00								2		12.00 X ~~12.75~~								INSTALL 110 FT ± NORTH OF EXISTING SIGN AT MP 0.579	X		
NB	0.601	B	W1-6	48	24			8.00								2		12.25 X ~~12.75~~									X		
NB	0.633	A					SPEED LIMIT 40			1					X											5-23-18			
SIGN SUMMARY SHEET							SHEET TOTALS	~~56.75~~ ~~62.75~~	0.00	1	0	0	3	0	0	13		~~151.50~~ ~~195.0~~		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	220.5	0.0	1	0	0	14	0	0	44		660.0		0	0.0								

PROJECT NAME: **STATEWIDE-NORTH REGION**
PROJECT NUMBER: **STP HRRR(22)**

FILE NAME: **z14k100tssstiohnsburv TH8 l** PLOT DATE: **5/5/2017**
PROJECT MANAGER: **K. RUTTER** DRAWN BY: **R. SHEDD**
DESIGNED BY: **R. SHEDD** CHECKED **S. GOODWIN**
ST. JOHNSBURY TH-8 NORTHBOUND 1 SHEET **214** OF **255**