










DIRECTION	MILEPOINT	LOCATION CODE (SHEET 4)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS		EXISTING SIGNS			EXIST POST		NUMBER OF NEW POSTS	SQUARE STEEL (IN)			TUBULAR STEEL Ø (IN)				SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION				
								"A"	"B"	RETAIN	SALVAGE FROM	SALVAGE TO	REMOVE	RETAIN		REMOVE	1.75	2.00	2.50	FOUNDATION	3.00	3.50			4.00	5.00	SHSM	SIGN DETAIL SHEET #	STANDARD SHEET #
																	(LB / FT)				(LB / FT)								
NB ST JOHNSBURY TH-8							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN															"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS BOOK							
NB	0.660 - 0.700	A		6	8		INSTALL (5) NEW DELINEATOR POSTS															INSTALL (10) TYPE II 6"x8" WHITE DELINEATORS BACK TO BACK ON 5 NEW POSTS; INSTALL FIRST POST AT MP 0.660, 20 FT ± SOUTH OF UTILITY POLE 17/17 AT MP 0.664, THEN EVERY 55 FT ±, SEE SHEET 9							
NB	0.936	A	W1-4R	30	30			6.25							1	14.00 X						INSTALL 90 FT ± SOUTH OF EXISTING UTILITY POLE 93/CVPS/21/21 AT MP 0.953	X						
NB	1.00 - 1.039	A		6	8		INSTALL (4) NEW DELINEATOR POSTS															INSTALL (8) TYPE II 6"x8" WHITE DELINEATORS BACK TO BACK ON 4 NEW POSTS; INSTALL FIRST POST AT MP 1.00, 250 FT ± NORTH OF UTILITY POLE 93/CVPS/21/21 AT MP 0.953, THEN EVERY 70 FT ±, SEE SHEET 9							
NB	1.457	A					SPEED LIMIT 40																						
NB	1.527	A	W1-10L	36	36			9.00														INSTALL 115 FT ± SOUTH OF EXISTING SIGN AT MP 1.549	X						
		A	W16-8p	36	8			2.00																21					
		A	W13-1p	18	18			2.25														INSTALL ON LEFT POST	X						
NB	1.549	B	W1-8				RIGHT CHEVRON																						
																													
NB	1.549	A	W1-6	48	24			8.00															X						
NB	1.550	B	W1-6	48	24			8.00															X						
NB	1.560	AB	D3-1				MUD HOLLOW																						
NB	1.566	AB	D3-1	64	12		 	5.33																21					
NB	1.566	D	R1-1	30	30			6.25															X						
SIGN SUMMARY SHEET							SHEET TOTALS	47.08	0.00	0	0	0	3	0	0	10	131.50 150.0	0	0.0	0.0	0.0	0.0	PROJECT NAME: STATEWIDE-NORTH REGION PROJECT NUMBER: STP HRRR(22)						
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	220.5	0.0	1	0	0	14	0	0	44	660.0	0			0.0		FILE NAME: z14k100tssstionhsburv TH8 PLOT DATE: 5/5/2017 PROJECT MANAGER: K. RUTTER DRAWN BY: R. SHEDD DESIGNED BY: R. SHEDD CHECKED: S. GOODWIN ST. JOHNSBURY TH-8 NORTHBOUND 2 SHEET 215 OF 255						

9 DEL.