DIRECTION	MILEPOINT	LOCATION CODE (SHEET 4)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB/FT) 1.88	SQUARE STEEL (IN) 2.00 (LB/FT) 2.42	SQUARE STEEL (IN) 2.50 (LB/FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB/FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB/FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB/FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB/FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION SIGN DETAIL SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
NB ST JOHNSBURY TH-8							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS BOOK			
NB	1.574	A	W1-8				LEFT CHEVRON						1		X											5-23-18			
NB	1.574	A	W1-6	48	24			8.00								2		13.25 X 13.00									X		
NB	1.575	B	W1-6	48	24			8.00								2		13.00 X 12.75									X		
NB	2.129	A	VW-133R				HIDDEN DRIVE RIGHT						1		X											5-24-18			
		A	VW-133R	30	30			6.25								1		14.00 X											T-81
NB	2.446	AB	D3-1				DILLON DR						1		X											5-25-18			
		AB	D3-1	40	12		Dillon Dr	3.33																		MOUNT DILLON DR PERP ON TOP OF STOP SIGN		21	
		D	R1-1	30	30		STOP	6.25								1		13.75 X									X		
NB	2.706	D	R1-1	30	30		STOP	6.25								1		14.00 X								5-30-18	X		
NB	2.706	AB	D3-1				WILLEY FARM RD						1		X											5-25-18			
		AB	D3-1	64	12		Willey Farm Rd	5.33								2		11.75 X 12.50										21	
NB	2.715	D	R1-1	30	30		STOP	6.25								1		12.50 X									X		
NB	2.739	A	R2-1	24	30		SPEED LIMIT 40	5.00								1		12.75 X								5-28-18 INSTALL 190 FT ± SOUTH OF EXISTING SIGN AT MP 2.775	X		
NB	2.775	A	R2-1				SPEED LIMIT 40						1		X														
SIGN SUMMARY SHEET							SHEET TOTALS	54.67	0.00	0	0	0	5	0	0	11		143.25 ~~165.0~~		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	220.5	0.0	1	0	0	14	0	0	44		660.0		0	0.0								

PROJECT NAME: **STATEWIDE-NORTH REGION**
PROJECT NUMBER: **STP HRRR(22)**

FILE NAME: **z14k100tssstiohnsburv TH8 I** PLOT DATE: **5/5/2017**
PROJECT MANAGER: **K. RUTTER** DRAWN BY: **R. SHEDD**
DESIGNED BY: **R. SHEDD** CHECKED **S. GOODWIN**
ST. JOHNSBURY TH-8 NORTHBOUND 3 SHEET **216** OF **255**