



DIRECTION	MILEPOINT	LOCATION CODE (SHEET 4)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS		EXISTING SIGNS			EXIST POST		NUMBER OF NEW POSTS	SQUARE STEEL (IN)			TUBULAR STEEL Ø (IN)				SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION				
								"A"	"B"	RETAIN	SALVAGE FROM	SALVAGE TO	REMOVE	RETAIN		REMOVE	1.75	2.00	2.50	FOUNDATION	3.00	3.50			4.00	5.00	SHSM	SIGN DETAIL SHEET #	STANDARD SHEET #
																	(LB / FT)				(LB / FT)								
WB UNDERHILL TH-1							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN															"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS BOOK							
WB	0.355 - 0.312	F		6	8		INSTALL (4) NEW DELINEATOR POSTS															INSTALL (8) TYPE II 6"x8" WHITE DELINEATORS BACK TO BACK ON 4 NEW POSTS; INSTALL THE FIRST POST 5 FT ± EAST OF UTILITY POLE 31/25/24, THEN EVERY 75 FT ±, SEE SHEET 9							
WB	0.083	F	D3-1				MAPLE RIDGE RD				1		X									5-7-18							
		F	D3-1	64	12			5.33						2		10.00 X 10.00								21					
WB	0.076	F	R1-1	30	30			6.25						1		10.75 X								X					
WB	0.055	F	W3-5				SPEED LIMIT 25 AHEAD			1			X																
SIGN SUMMARY SHEET							SHEET TOTALS	11.58	0.00	1	0	0	1	0	0	3	30.75 45.0	0	0.0	0.0	0.0	0.0	PROJECT NAME: STATEWIDE-NORTH REGION PROJECT NUMBER: STP HRRR(22)						
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	11.6	0.0	1	0	0	1	0	0	3	45.0	0		0.0			FILE NAME: z14k100tssunderhill TH1 WB. PLOT DATE: 5/5/2017 PROJECT MANAGER: K. RUTTER DRAWN BY: R. SHEDD DESIGNED BY: R. SHEDD CHECKED: S. GOODWIN UNDERHILL TH-1 WESTBOUND 1 SHEET 225 OF 255						

4 DEL.