DIRECTION	MILEPOINT	LOCATION CODE (SHEET 4)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION SIGN DETAIL SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
EB WARREN TH-5							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS BOOK			
EB	1.106	AB	D3-1				STERLING RIDGE RD			1				X															
EB	1.128	A	W7-1				HILL WARNING						1		X												5-31-18		
		A	W1-4R	30	30			6.25								1		15.25 X									X		
		A	W13-1p	18	18			2.25																			X		
EB	1.280	A	S3-1	36	36	FYG		9.00								2		14.00 X ~~14.75~~								6-1-18 INSTALL 130 FT ± WEST OF UTILITY POLE GMP/10/519 AT MP 1.305	X		
EB	1.525	A	R2-1				SPEED LIMIT 40			1				X															
EB	1.639	A	W1-2R				RIGHT CURVE						1		X															
		A	OM1-1				OBJECT MARKER						1																	
		A	W1-2R	30	30			6.25								1		15.25 X									X		
		A	W13-1p	18	18			2.25																			X		
EB	1.798	A	W1-2L	30	30			6.25								1		14.75 X								INSTALL 70 FT ± WEST OF UTILITY POLE GMP/20530/1041/35S AT MP 1.811	X		
EB	1.935	A	W7-1	30	30			6.25								1		13.75 X									X		
EB	2.073	A	R2-1				SPEED LIMIT 40			1				X															
EB	2.248	A	S3-1	36	36	FYG		9.00								2		14.75 X ~~16.25~~								6-5-18 INSTALL 45 FT ± WEST OF UTILITY POLE GMP/31/1067/46 AT MP 2.257	X		
EB	2.315	A	S3-1				SCHOOL BUS STOP AHEAD						1		X															
SIGN SUMMARY SHEET							SHEET TOTALS	47.50	0.00	3	0	0	4	0	0	8		~~120.0~~ 118.75		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	200.0	0.0	14	2	2	23	0	0	35		525.0		0	0.0								

PROJECT NAME: **STATEWIDE-NORTH REGION**
PROJECT NUMBER: **STP HRRR(22)**
FILE NAME: **z14k100tsswarrenTH5 EB.xls** PLOT DATE: **5/5/2017**
PROJECT MANAGER: **K. RUTTER** DRAWN BY: **R. SHEDD**
DESIGNED BY: **R. SHEDD** CHECKED **S. GOODWIN**
WARREN TH-5 EASTBOUND 4 SHEET **229** OF **255**