

# QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
								ROADWAY	EROSION CONTROL	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
								1			1		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	--			
								200			200		HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST.			
								400			400		HR	FLAGGERS	630.15	EST.			
										1	1		LS	TESTING EQUIPMENT, CONCRETE	631.16	--			
								1			1		LS	MOBILIZATION/DEMOBILIZATION	635.11	--			
								2			2		EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	--			
									20		20		LB	SEED	651.15	EST.			
									50		50		LB	FERTILIZER	651.18	EST.			
									0.1		0.1		TON	HAY MULCH	651.25	EST.			
								3			3		CY	TOPSOIL	651.35	EST.			
								15			15		SF	TRAFFIC SIGNS, TYPE A	675.20	--			
								1			1		EACH	TRAFFIC CONTROL SIGNAL SYSTEM, INTERSECTION	678.15	--			
								450			450		LF	ELECTRICAL CONDUIT (2" DIA.)(SCH. 80)	678.21	3			
								900			900		LF	WIRED CONDUIT (2" DIA.)(SCH. 80)	678.23	13			
								1			1		EACH	REMOVAL OF EXISTING TRAFFIC CONTROL SIGNAL SYSTEM	678.45	--			
								3			3		EACH	BRACKET ARM	679.47	--			
								3			3		EACH	LUMINAIRE (LUMINAIRE, LED)	679.50	--			
								1			1		EACH	STREET LIGHT CONTROL DEVICE	679.54				
								4			4		EACH	SPECIAL PROVISION (JUNCTION BOX, HEAVY DUTY)	900.620	--			
								225			225		LF	SPECIAL PROVISION (HORIZONTAL DIRECTIONAL DRILLING)(10" CASING PIPE)	900.640	6			
								1			1		LS	SPECIAL PROVISION (TRAFFIC CONTROL, ALL INCLUSIVE)	900.645	--			

PROJECT NAME: RUTLAND TOWN  
PROJECT NUMBER: NHG 019-3(60)  
FILE NAME: t14t190frm.dgn PLOT DATE: 2/7/2017  
PROJECT LEADER: P. COBURN DRAWN BY: M. BOGACZYK  
DESIGNED BY: M. BOGACZYK CHECKED BY: P. COBURN  
QUANTITY SHEET SHEET 8 OF 17