STATE OF VERMONT
AGENCY OF TRANSPORTATION

QUANTITY SHEET 3

SUMMARY OF ESTIMATED QUANTITIES

ROADWAY	RAILROAD - BID ITEMS	BRIDGE	FULL C.E. ITEMS	ROADWAY (ALT. A)	ROADWAY (ALT. B)	ROADWAY (ALT. C)	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND
1500							1500		LF	SPECIAL PROVISION (DURABLE 8 INCH YELLOW LINE, POLYUREA)(28 MILS)	900.640	8
650							650		LF	SPECIAL PROVISION (DURABLE CROSSWALK MARKING, POLYUREA)(28 MILS)	900.640	48
	1						1		LU	SPECIAL PROVISION (MAINTENANCE OF RAILROAD TRAFFIC)(N.A.B.I.)	900.650	-
2500							2500		SY	SPECIAL PROVISION (HAND-PLACED BITUMINOUS CONCRETE MATERIAL, DRIVES)	900.675	EST.
475000							475000		SY	SPECIAL PROVISION (MICRO-MILLING BITUMINOUS CONCRETE PAVEMENT)	900.675	657
200							200		TON	SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT SURFACE PREPARATION, TYPE I)	900.680	EST.
660							660		CWT	SPECIAL PROVISION (FOG SEAL SURFACE TREATMENT)	900.683	EST.
										BEGIN ALTERNATE ZA1		
				615000			615000		SY	SPECIAL PROVISION (PAVER PLACED SURFACE TREATMENT, TYPE C)(PG 70-28)(SBR OR SBS POLYMER)	900.675	326
										END ALTERNATE ZA1		
										BEGIN ALTERNATE ZA2		
					3400		3400		CWT	EMULSIFIED ASPHALT	404.65	EST.
					1		1		LU	AIR VOIDS PAY ADJUSTMENT (N.A.B.I.)	490.31	-
					35400		35400		TON	SPECIAL PROVISION (6.3 MM POLYMER MODIFIED BITUMIN. CONC. PAVEMENT)(PG 70-28)(SBR OR SBS POLYMER)	900.680	54
										END ALTERNATE ZA2		
										BEGIN ALTERNATE ZA3		
						1	1		LU	AIR VOIDS PAY ADJUSTMENT (N.A.B.I.)	490.31	-
						35400	35400		TON	SPECIAL PROVISION (6.3 MM POLYMER MODIFIED BITUMIN. CONC. PAVEMENT)(PG 70-28)(SBR OR SBS POLYMER)	900.680	54
						3400	3400		CWT	SPECIAL PROVISION (EMULSIFIED ASPHALT)(RS-1H OR CRS-1H)	900.683	EST.
										END ALTERNATE ZA3		

DETAILED SUMMARY OF QUANTITIES

SPECIAL PROVISION(MICRO-MILLING BITUMINOUS CONCRETE PAVEMENT)

QUANTITIES	UNIT	ITEMS
		MANCHESTER - US7
1943	SY	BRIDGE 27
		DORSET - US7
11982	SY	BRIDGE 30 APPROACH TO MM 1.745
		WALLINGFORD - US7
116536	SY	TWO-LANE HIGHWAY
12395	SY	SOUTHBOUND - LIMITED ACCESS
12414	SY	NORTHBOUND - LIMITED ACCESS
		CLARENDON - US7
127147	SY	SOUTHBOUND - LIMITED ACCESS
129476	SY	NORTHBOUND - LIMITED ACCESS
		RUTLAND TOWN - US7
16556	SY	SOUTHBOUND
15639	SY	NORTHBOUND
20708	SY	UNDIVIDED HIGHWAY
9547	SY	PAVED APRONS & SIDE LINES
657	SY	ROUNDING
475000	SY	TOTAL

ALTERNATE (ZA1)

QUANTITIES	UNIT	ITEMS
		SPECIAL PROVISION (PAVER PLACED SURFACE TREATMENT, TYPE C)
		MANCHESTER - US7
87201	SY	MAINLINE & RAMPS
		DORSET - US7
52407	SY	MAINLINE
		WALLINGFORD - US7
120153	SY	TWO-LANE HIGHWAY
12395	SY	SOUTHBOUND - LIMITED ACCESS
12414	SY	NORTHBOUND - LIMITED ACCESS
		CLARENDON - US7
127147	SY	SOUTHBOUND - LIMITED ACCESS
129476	SY	NORTHBOUND - LIMITED ACCESS
		RUTLAND TOWN - US7
16556	SY	SOUTHBOUND
15639	SY	NORTHBOUND
20708	SY	UNDIVIDED HIGHWAY
20579	SY	PAVED APRONS & SIDE LINES
326	SY	ROUNDING
615000	SY	TOTAL

ALTERNATE (ZA2)/(ZA3)

QUANTITIES	UNIT	ITEMS
		SPECIAL PROVISION (6.3MM POLYMER-MODIFIED BITUMINOUS CONCRETE PAVEMENT)(SBR OR SBS POLYMER)
		MANCHESTER - US7
5085	TON	MAINLINE & RAMPS
		DORSET - US7
3056	TON	MAINLINE
		WALLINGFORD - US7
7006	TON	TWO-LANE HIGHWAY
723	TON	SOUTHBOUND - LIMITED ACCESS
724	TON	NORTHBOUND - LIMITED ACCESS
		CLARENDON - US7
7414	TON	SOUTHBOUND - LIMITED ACCESS
7550	TON	NORTHBOUND - LIMITED ACCESS
		RUTLAND TOWN - US7
965	TON	SOUTHBOUND
912	TON	NORTHBOUND
1207	TON	UNDIVIDED HIGHWAY
704	TON	PAVED APRONS & SIDE LINES
54	TON	ROUNDING
35400	TON	TOTAL

PROJECT NAME: MANCHESTER-RUTLAND TOWN
PROJECT NUMBER: NH SURF(50)

FILE NAME: pl4v200frm.dgn
PROJECT LEADER: M. FOWLER
DESIGNED BY: B. KIPP
QUANTITY SHEET 3

PLOT DATE: 1/15/2016
DRAWN BY: B. KIPP
CHECKED BY: M. FOWLER
SHEET 14 OF 105