

# COMPOSITE QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
				ROADWAY BENNINGTON- WILMINGTON	ROADWAY POWNAI- BENNINGTON	ROADWAY BENN.-WILM. (NO PART.)	EROSION CONTROL BENN.-WILM.	BRIDGE BENNINGTON- WILMINGTON	FULL C & E ITEMS BENN- WILM.	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
				95000						95000		LF	SHOULDER BERM REMOVAL	203.40	609			
				1						1		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	EST			
				14300						14300		SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10	446			
				78300	31900					110200		LF	MILLED RUMBLE STRIPS (CENTERLINE)	213.10	634			
				5600						5600		TON	SUBBASE OF CRUSHED GRAVEL, FINE GRADED	301.28	96			
													BEGIN OPTION AA					
				2000						2000		TON	AGGREGATE SHOULDERS	402.12	104			
				2000						2000		TON	AGGREGATE SHOULDERS, RAP	402.13	104			
													END OPTION AA					
													BEGIN OPTION BB					
				375						375		CWT	EMULSIFIED ASPHALT	404.65	24			
				375						375		CWT	SPECIAL PROVISION (EMULSIFIED ASPHALT)(RS-1H)(CRS-1H)	900.683	24			
													END OPTION BB					
				1	1					2		LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50	-			
				35200						35200		LB	BITUMINOUS CRACK SEALING, "BLOW AND GO" METHOD (AASHTO M 324 (ASTM D 6690) TYPE II)	417.20	338			
				8800						8800		TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT(PG 70-28)	490.30	70			
				1						1		LU	AIR VOIDS PAY ADJUSTMENT (N.A.B.I.)	490.31	-			
										312		LF	BRIDGE EXPANSION JOINT, ASPHALTIC PLUG (@FINGER PLATE/VERMONT JOINT)	516.10	EST			
										570		LF	BRIDGE EXPANSION JOINT, ASPHALTIC PLUG	516.10	EST			
										100		CF	RAPID SETTING CONCRETE REPAIR MATERIAL WITH COARSE AGGREGATE	580.20	EST			
				81						81		EACH	CHANGING ELEVATION OF DROP INLETS, CATCH BASINS, OR MANHOLES	604.40	-			
				32		22				54		EACH	CHANGING ELEVATION OF SEWER MANHOLES	604.42	-			
				525						525		HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	EST			
				125						125		HR	POWER BROOM RENTAL, TYPE I	608.30	EST			
				200						200		HR	POWER BROOM RENTAL, TYPE II	608.31	EST			
				1075						1075		HR	TRUCK RENTAL	608.37	EST			
				525						525		HR	LOADER RENTAL, TYPE I	608.40	EST			
						10				10		EACH	ADJUST ELEVATION OF VALVE BOX	629.20	-			
				2000	140					2140		HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST			
				10000						10000		HR	FLAGGERS	630.15	EST			
										1		LS	FIELD OFFICE, ENGINEERS	631.10	-			
										1		LS	TESTING EQUIPMENT, BITUMINOUS	631.17	-			
										3000		DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26	-			
				520						520		HR	EMPLOYEE TRAINEESHIP	634.10	-			
				1						1		LS	MOBILIZATION/DEMOBILIZATION (NH SURF(51))	635.11	-			
				1						1		LS	TRAFFIC CONTROL ((NH SURF(51))	641.10	-			
					1					1		LS	TRAFFIC CONTROL (NH RMBL(3))	641.10	-			
				6						6		EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	-			
					63					63		DAY	PORTABLE CHANGEABLE MESSAGE SIGN RENTAL	641.17	-			

PROJECT NAME: POWNAL - BENNINGTON &  
BENNINGTON - WILMINGTON  
PROJECT NUMBER: NH RMBL (3) & NH SURF (51)

FILE NAME: p14v201Bennington-Wilmington.dgRLOT DATE: 06-APR-2017  
PROJECT LEADER: M. FOWLER DRAWN BY: N. PAPPAS  
DESIGNED BY: N. PAPPAS CHECKED BY: M. FOWLER  
COMPOSITE QUANTITY SHEET 1 SHEET 4 OF 64