

STATE OF VERMONT AGENCY OF TRANSPORTATION												COMPOSITE QUANTITY SHEET 2											
SUMMARY OF ESTIMATED QUANTITIES												TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES					
						ROADWAY BENNINGTON- WILMINGTON	ROADWAY POWNAL- BENNINGTON	ROADWAY BENN.-WILM. (NO PART.)	EROSION CONTROL BENN.-WILM.	BRIDGE BENNINGTON- WILMINGTON	FULL C & E ITEMS BENN.- WILM.	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS			
																BEGIN OPTION CC							
						700						700		LF	DURABLE 24 INCH STOP BAR, THERMOPLASTIC	646.482	EST						
						700						700		LF	SPECIAL PROVISION (DURABLE 24 INCH STOP BAR, EPOXY)(24MILS)	900.640	EST						
						700						700		LF	SPECIAL PROVISION (DURABLE 24 INCH STOP BAR, POLYUREA)(24MILS)	900.640	EST						
															END OPTION CC								
															BEGIN OPTION DD								
						217						217		EACH	DURABLE LETTER OR SYMBOL, THERMOPLASTIC	646.492	-						
						217						217		EACH	SPECIAL PROVISION (DURABLE LETTER OR SYMBOL, EPOXY)(28 MILS)	900.620	-						
						217						217		EACH	SPECIAL PROVISION (DURABLE LETTER OR SYMBOL, POLYUREA)(28 MILS)	900.620	-						
															END OPTION DD								
															BEGIN OPTION EE								
						400						400		LF	DURABLE CROSSWALK MARKING, THERMOPLASTIC	646.502	EST						
						400						400		LF	SPECIAL PROVISION (DURABLE CROSSWALK MARKING, EPOXY)(28 MILS)	900.640	EST						
						400						400		LF	SPECIAL PROVISION (DURABLE CROSSWALK MARKING, POLYUREA)(28 MILS)	900.640	EST						
															END OPTION EE								
						307900						307900		LF	TEMPORARY 4 INCH WHITE LINE, PAINT	646.602	EST						
						285700						285700		LF	TEMPORARY 4 INCH YELLOW LINE, PAINT	646.612	EST						
						280						280		LF	TEMPORARY 6 INCH WHITE LINE, PAINT	646.622	EST						
						210						210		LF	TEMPORARY 6 INCH YELLOW LINE, PAINT	646.632	EST						
						775						775		LF	TEMPORARY 8 INCH WHITE LINE, PAINT	646.642	EST						
						700						700		LF	TEMPORARY 8 INCH YELLOW LINE, PAINT	646.652	EST						
						700						700		LF	TEMPORARY 24 INCH STOP BAR, PAINT	646.682	EST						
						217						217		EACH	TEMPORARY LETTER OR SYMBOL, PAINT	646.692	-						
						400						400		LF	TEMPORARY CROSSWALK MARKING, PAINT	646.702	EST						
						49500	10800					60300		EACH	LINE STRIPING TARGETS	646.76	EST						
									500			500		LB	SEED	651.15	EST						
									500			500		LB	FERTILIZER	651.18	EST						
									2			2		TON	AGRICULTURAL LIMESTONE	651.20	EST						
									2			2		TON	HAY MULCH	651.25	EST						
						1						1		EACH	TRAFFIC CONTROL SIGNAL SYSTEM, INTERSECTION	678.15	-						
						1						1		LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50	-						
															BEGIN OPTION FF								
						249900						249900		LF	SPECIAL PROVISION (DURABLE 4 INCH WHITE LINE, EPOXY)(28 MILS)	900.640	EST						
						249900						249900		LF	SPECIAL PROVISION (DURABLE 4 INCH WHITE LINE, POLYUREA)(28 MILS)	900.640	EST						
															END OPTION FF								
															BEGIN OPTION GG								
						250500	31900					282400		LF	SPECIAL PROVISION (DURABLE 4 INCH YELLOW LINE, EPOXY)(28 MILS)	900.640	EST						
						250500	31900					282400		LF	SPECIAL PROVISION (DURABLE 4 INCH YELLOW LINE, POLYUREA)(28 MILS)	900.640	EST						
															END OPTION GG								

PROJECT NAME:	POWNAL - BENNINGTON & BENNINGTON - WILMINGTON
PROJECT NUMBER:	NH RMBL (3) & NH SURF (51)
FILE NAME:	pl4v201Bennington-Wilmington.dg
PROJECT LEADER:	M. FOWLER
DESIGNED BY:	N. PAPPAS
COMPOSITE QUANTITY SHEET 2	
DATE:	06-APR-2017
DRAWN BY:	N. PAPPAS
CHECKED BY:	M. FOWLER
SHEET 5	OF 64