

COMPOSITE QUANTITY SHEET 3

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
				ROADWAY BENNINGTON- WILMINGTON	ROADWAY POWNAI- BENNINGTON	ROADWAY BENN.-WILM. (NO PART.)	EROSION CONTROL BENN.-WILM.	BRIDGE BENNINGTON- WILMINGTON	FULL C & E ITEMS BENN- WILM.	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
													BEGIN OPTION HH					
				280						280		LF	SPECIAL PROVISION (DURABLE 6 INCH WHITE LINE, EPOXY)(28 MILS)	900.640	EST			
				280						280		LF	SPECIAL PROVISION (DURABLE 6 INCH WHITE LINE, POLYUREA)(28 MILS)	900.640	EST			
													END OPTION HH					
													BEGIN OPTION II					
				210						210		LF	SPECIAL PROVISION (DURABLE 6 INCH YELLOW LINE, EPOXY)(28 MILS)	900.640	EST			
				210						210		LF	SPECIAL PROVISION (DURABLE 6 INCH YELLOW LINE, POLYUREA)(28 MILS)	900.640	EST			
													END OPTION II					
													BEGIN OPTION JJ					
				775						775		LF	SPECIAL PROVISION (DURABLE 8 INCH WHITE LINE, EPOXY)(28 MILS)	900.640	EST			
				775						775		LF	SPECIAL PROVISION (DURABLE 8 INCH WHITE LINE, POLYUREA)(28 MILS)	900.640	EST			
													END OPTION JJ					
													BEGIN OPTION KK					
				700						700		LF	SPECIAL PROVISION (DURABLE 8 INCH YELLOW LINE, EPOXY 28 MILS)	900.640	EST			
				700						700		LF	SPECIAL PROVISION (DURABLE 8 INCH YELLOW LINE, POLYUREA)(28 MILS)	900.640	EST			
													END OPTION KK					
				13400						13400		SY	SPECIAL PROVISION (HAND-PLACED BITUMINOUS CONCRETE MATERIAL, DRIVES)	900.675	EST			
				395000						395000		SY	SPECIAL PROVISION (MICRO-MILLING BITUMINOUS CONCRETE PAVEMENT)	900.675	2808			
				432750						432750		SY	SPECIAL PROVISION (PAVER PLACED SURFACE TREATMENT, TYPE C)(PG 70-28)(SBS POLYMER)	900.675	2815			
				250						250		TON	SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT SURFACE PREPARATION, TYPE I)	900.680	EST			
				230	100					330		CWT	SPECIAL PROVISION (FOG SEAL SURFACE TREATMENT)	900.683	19			

PROJECT NAME: POWNAI - BENNINGTON &
BENNINGTON - WILMINGTON
PROJECT NUMBER: NH RMBL (3) & NH SURF (5 I)

FILE NAME: p14v201Bennington-Wilmington.dg PLOT DATE: 06-APR-2017
PROJECT LEADER: M. FOWLER DRAWN BY: N. PAPPAS
DESIGNED BY: N. PAPPAS CHECKED BY: M. FOWLER
COMPOSITE QUANTITY SHEET 3 SHEET 6 OF 64