

INDEX OF SHEETS

1

TITLE SHEET

2

INDEX SHEET

3

CONVENTIONAL SYMBOLOGY - LEGEND

4-6

COMPOSITE QUANTITY SHEETS

7

P-B TITLE SHEET

8

P-B PROJECT NOTES

9

P-B QUANTITY SHEET

10

P-B CONSTRUCTION APPROACH SIGNING SHEET

11

B-W TITLE SHEET

12

B-W PROJECT NOTES

13-14

B-W TYPICAL SECTIONS

15

B-W DETAIL SHEETS

16

B-W PROJECT COLD PLANE DETAILS

17-19

B-W QUANTITY SHEETS

20-55

B-W LAYOUT SHEETS

56

B-W TRAFFIC SIGNAL SYSTEM SHEET

57

B-W TRAFFIC SIGNAL SYSTEM NOTES SHEET

58-60

B-W BRIDGE EXPANSION JOINT DETAIL SHEETS

61

B-W VERMONT JOINT ASPHALTIC PLUG DETAIL SHEET

62

B-W RUTTING DATA INFORMATION SHEET

63

B-W ROUGHNESS DATA INFORMATION SHEET

64

B-W CONSTRUCTION APPROACH SIGNING SHEET

DETAIL SHEETS

STRUCTURAL DETAIL SD-516.10

08-29-11

MILLED RUMBLE STRIP (CENTERLINE) DETAILS HSD-213.02

02-13-17

SAFETY EDGE DETAIL HSD-400.01

03-29-16

VAOT STANDARDS

T-1

04/25/16

T-10

08/06/12

T-17

08/06/12

T-28

08/06/12

T-29

08/06/12

T-30

08/06/12

T-31

08/06/12

T-35

08/06/12

T-36

08/06/12

T-80

02/12/16

E-191

02/01/99

E-192

10/12/00

E-193

08/18/95

TRAFFIC DATA

VT ROUTE 7 NORTHBOUND	ADT		DHV		ESAL'S	ESAL'S
	2017	2027	2017	2027	2017-2027	2017-2037
BEGIN PROJECT TO VT 346	6,800	7,000	740	760	1,591,000	3,581,000
VT 346 TO BARBER POND RD	5,300	5,400	600	610	773,000	1,806,000
BARBER POND RD TO JACKSON CROSS RD	5,800	5,900	650	660	849,000	1,806,000
JACKSON CROSS RD TO MONUMENT AVE. EXT.	6,500	6,700	730	750	825,000	1,881,000
MONUMENT AVE. EXT. TO END PROJECT	5,700	5,800	600	610	902,000	2,059,000

VT ROUTE 9 EASTBOUND	ADT		DHV		ESAL'S	ESAL'S
	2017	2027	2017	2027	2017-2027	2017-2037
BEGINNING OF PROJECT US ROUTE 9 (MM 5.672) TO VT ROUTE 279 IN BENNINGTON (MM 5.785)	4,200	4,500	680	720	649,000	1,530,000
VT ROUTE 279 TO HARBOUR RD IN WOODFORD (MM 1.422)	5,200	5,500	840	890	1,734,000	3,989,000
HARBOUR ROAD TO VT ROUTE 8 IN SEARSBURG (MM 1.822)	3,600	3,800	580	610	1,574,000	3,420,000
VT ROUTE 8 TO VT ROUTE 100N IN WILMINGTON (MM 3.088)	4,000	4,300	640	690	1,809,000	4,186,000
VT ROUTE 100N TO VT 100S IN WILMINGTON (MM 4.158)	11,100	11,800	1,400	1,500	2,432,000	5,571,000
VT ROUTE 100S TO END OF PROJECT (MM 7.160)	4,800	5,100	640	680	2,101,000	4,612,000