COMPOSITE QUANTITY SHEET 1

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

JOHNSON - HYDE PARK STP SURF(52)						BELVIDERE - BERKSHIRE STP SURF(53)										
	ROADWAY ALT. A	ROADWAY ALT. B	BRIDGE	ROADWAY	FULL C.E.	ROADWAY ALT. A	ROADWAY ALT. B	BRIDGE	ROADWAY	FULL C.E.	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
													BEGIN ITEMS COMMON TO ALL ALTERNATES		
				7,750					29,500		37,250	LF	SHOULDER BERM REMOVAL	203.40	EST
				1					1		2	CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	-
				6,065					14,810		20,875	LF	MILLED RUMBLE STRIPS (CENTERLINE)	213.10	EST
													BEGIN OPTION AA		
				450					1,500		1,950	TONS	AGGREGATE SHOULDERS	402.12	192
				450					1,500		1,950	TONS	AGGREGATE SHOULDERS, RAP	402.13	192
													END OPTION AA		
				1					1		2	LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50	-
				4,750					15,500		20,250	LB	BITUMINOUS CRACK SEALING, "BLOW AND GO" METHOD (AASHTO M 324 (ASTM D 6690) TYPE II)	417.20	511
			80					520			600	LF	BRIDGE EXPANSION JOINT, ASPHALTIC PLUG	516.10	10
								250			250	LF	BRIDGE EXPANSION JOINT, ASPHALTIC PLUG (@ FINGER PLATE/VERMONT JOINT)	516.10	6
			50					50			100	CF	RAPID SETTING CONCRETE REPAIR MATERIAL WITH COARSE AGGREGATE	580.20	EST
				2					20		22	EA	CHANGING ELEVATION OF DI, CB, OR MH	604.40	-
				50					100		150	HR	POWER BROOM RENTAL, TYPE I	608.30	EST
				100					100		200	HR	POWER BROOM RENTAL, TYPE II	608.31	EST
				100					100		200	HR	TRUCK RENTAL	608.37	EST
									3		3	EA	ADJUST ELEVATION OF VALVE BOX	629.20	-
				200					450		650	HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST
				1,000					2,250		3,250	HR	FLAGGERS	630.15	EST
					0.5					0.5	1	LS	FIELD OFFICE, ENGINEERS	631.10	-
					0.5					0.5	1	LS	TESTING EQUIPMENT, BITUMINOUS	631.17	-
					1,500					1,500	3,000	DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26	-
				0.5					0.5		1	LS	MOBILIZATION/DEMOBILIZATION	635.11	-
				1							1	LS	TRAFFIC CONTROL (STP SURF(52))	641.10	-
									1		1	LS	TRAFFIC CONTROL (STP SURF(53))	641.10	-
				4					5		9	EA	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	EST
													BEGIN OPTION BB		
				170					360		530	LF	DURABLE 24 INCH STOP BAR, THERMOPLASTIC	646.482	EST
				170					360		530	LF	SPECIAL PROVISION (DURABLE 24 INCH STOP BAR, POLYUREA) (28 MIL)	900.640	EST
													END OPTION BB		
													BEGIN OPTION CC		
				58											
									89		147	EA	DURABLE LETTER OR SYMBOL, THERMOPLASTIC	646.492	-
				58											
									89		147	EA	SPECIAL PROVISION (DURABLE LETTER OR SYMBOL, POLYUREA) (28 MIL)	900.620	-
													END OPTION CC		

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

PROJECT NAME: JOHNSON - HYDE PARK, BELVIDERE - BERKSHIRE
PROJECT NUMBER: STP SURF(52), STP SURF(53)

FILE NAME: 14v204\pl4v204.dgn\pl4v204_09.1 PLOT DATE: 04-NOV-2015
PROJECT LEADER: M. FOWLER DRAWN BY: K. LOCKE
DESIGNED BY: K. LOCKE CHECKED BY: M. FOWLER
COMPOSITE QUANTITY SHEET 1 SHEET 9 OF 45