QUANTITY SHEET 1

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

ROADWAY ALT. A	ROADWAY ALT. B	BRIDGE	ROADWAY	FULL C.E.	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
							BEGIN ITEMS COMMON TO ALL ALTERNATES		
			7,750		7,750	LF	SHOULDER BERM REMOVAL	203.40	EST
			1		1	CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	-
			6,065		6,065	LF	MILLED RUMBLE STRIPS (CENTERLINE)	213.10	EST
							BEGIN OPTION AA		
			450		450	TON	AGGREGATE SHOULDERS	402.12	44
			450		450	TON	AGGREGATE SHOULDERS, RAP	402.13	44
							END OPTION AA		
			1		1	LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50	-
			4,750		4,750	LB	BITUMINOUS CRACK SEALING, "BLOW AND GO" METHOD (AASHTO M 324 (ASTM D 6690) TYPE II)	417.20	185
		80			80	LF	BRIDGE EXPANSION JOINT, ASPHALTIC PLUG	516.10	4
		50			50	CF	RAPID SETTING CONCRETE REPAIR MATERIAL WITH COARSE AGGREGATE	580.20	EST
			2		2	EA	CHANGING ELEVATION OF DI, CB, OR MH	604.40	-
			50		50	HR	POWER BROOM RENTAL, TYPE I	608.30	EST
			100		100	HR	POWER BROOM RENTAL, TYPE II	608.31	EST
			100		100	HR	TRUCK RENTAL	608.37	EST
			200		200	HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST
			1,000		1,000	HR	FLAGGERS	630.15	EST
				0.5	0.5	LS	FIELD OFFICE, ENGINEERS	631.10	-
				0.5	0.5	LS	TESTING EQUIPMENT, BITUMINOUS	631.17	-
				1,500	1,500	DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26	-
			0.5		0.5	LS	MOBILIZATION/DEMOBILIZATION	635.11	-
			1		1	LS	TRAFFIC CONTROL (STP SURF(52))	641.10	-
			4		4	EA	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	EST
							BEGIN OPTION BB		
			170		170	LF	DURABLE 24 INCH STOP BAR, THERMOPLASTIC	646.482	EST
			170		170	LF	SPECIAL PROVISION (DURABLE 24 INCH STOP BAR, POLYUREA) (28 MIL)	900.640	EST
							END OPTION BB		
							BEGIN OPTION CC		
			58		58	EA	DURABLE LETTER OR SYMBOL, THERMOPLASTIC	646.492	-
			58		58	EA	SPECIAL PROVISION (DURABLE LETTER OR SYMBOL, POLYUREA) (28 MIL)	900.620	-
							END OPTION CC		
			48,500		48,500	LF	TEMPORARY 4 INCH WHITE LINE, PAINT	646.602	EST
			46,000		46,000	LF	TEMPORARY 4 INCH YELLOW LINE, PAINT	646.612	EST
			170		170	LF	TEMPORARY 24 INCH STOP BAR, PAINT	646.682	EST
			58		58	EA	TEMPORARY LETTER OR SYMBOL, PAINT	646.692	-

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

PROJECT NAME: JOHNSON - HYDE PARK
PROJECT NUMBER: STP SURF(52)

FILE NAME: I4v204\pI4v204.dgn\pI4v204_I2.I
PROJECT LEADER: M. FOWLER
DESIGNED BY: K. LOCKE
QUANTITY SHEET I

PLOT DATE: 04-NOV-2015
DRAWN BY: K. LOCKE
CHECKED BY: M. FOWLER
SHEET 12 OF 45