

QUANTITY SHEET 2

**STATE OF VERMONT
AGENCY OF TRANSPORTATION**

SUMMARY OF ESTIMATED QUANTITIES								
ROADWAY ALT. A	ROADWAY ALT. B	ROADWAY ALT. C	ROADWAY	FULL C.E.	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO. ROUNDED
			9,650		9,650	EA	LINE STRIPING TARGETS	646.76
			38,690		38,690	SF	REMOVAL OF EXISTING PAVEMENT MARKINGS	646.85
			I		I	LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50
			48,500		48,500	LF	SPECIAL PROVISION (DURABLE 4 INCH WHITE LINE, POLYUREA) (28 MIL)	900.640
			46,000		46,000	LF	SPECIAL PROVISION (DURABLE 4 INCH YELLOW LINE, POLYUREA) (28 MIL)	900.640
			17,750		17,750	SY	SPECIAL PROVISION (MICRO-MILLING BITUMINOUS CONCRETE PAVEMENT)	900.675
			1,250		1,250	SY	SPECIAL PROVISION (HAND-PLACED BITUMINOUS CONCRETE MATERIAL, DRIVES)	900.675
			50		50	TON	SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT SURFACE PREPARATION, TYPE I)	900.680
			20		20	CWT	SPECIAL PROVISION (FOG SEAL SURFACE TREATMENT)	900.683
							END ITEMS COMMON TO ALL ALTERNATES	
							BEGIN ALTERNATE A	
			82,500		82,500	SY	SPECIAL PROVISION (PAVER PLACED SURFACE TREATMENT, TYPE C)	900.675
							END ALTERNATE A	
							BEGIN ALTERNATE B	
			600		600	CWT	EMULSIFIED ASPHALT (RS-I)	404.65
			I		I	LU	AIR VOIDS PAY ADJUSTMENT (N.A.B.I.)	490.31
			5,000		5,000	TON	SPECIAL PROVISION (6.3 MM POLYMER MODIFIED BITUMINOUS CONCRETE PAVEMENT)(SBR OR SBS POLYMER)	900.680
							END ALTERNATE B	
							BEGIN ALTERNATE C	
			I		I	LU	AIR VOIDS PAY ADJUSTMENT (N.A.B.I.)	490.31
			5,000		5,000	TON	SPECIAL PROVISION (6.3 MM POLYMER MODIFIED BITUMINOUS CONCRETE PAVEMENT)(SBR OR SBS POLYMER)	900.680
			600		600	CWT	SPECIAL PROVISION (EMULSIFIED ASPHALT)(RS-IH OR CRS-IH)	900.683
							END ALTERNATE C	

DETAILED SUMMARY OF QUANTITIES		
QUANTITIES	UNIT	ITEMS
		SPECIAL PROVISION (MICRO-MILLING BITUMINOUS CONCRETE PAVEMENT)
15,894	SY	MAINLINE
167	SY	BRIDGE 1 & 2 APPROACHES
996	SY	BRIDGE 6 APPROACH TO END OF PROJECT
629	SY	TOWN HIGHWAY APPROACHES
64	SY	ROUNDING
17,750	SY	TOTAL
		ALTERNATE A
		SPECIAL PROVISION (PAVER PLACED SURFACE TREATMENT, TYPE C)
81,328	SY	MAINLINE
629	SY	TOWN HIGHWAY APPROACHES
543	SY	ROUNDING
82,500	SY	TOTAL

DETAILED SUMMARY OF QUANTITIES		
QUANTITIES	UNIT	ITEMS
		ALTERNATE B
		SPECIAL PROVISION (6.3 MM POLYMER MODIFIED BITUMINOUS CONCRETE PAVEMENT)(SBR OR SBS POLYMER)
4,745	TON	MAINLINE
37	TON	TOWN HIGHWAY APPROACHES
218	TON	ROUNDING
5,000	TON	TOTAL
		ALTERNATE C
		SPECIAL PROVISION (6.3 MM POLYMER MODIFIED BITUMINOUS CONCRETE PAVEMENT)(SBR OR SBS POLYMER)
4,745	TON	MAINLINE
37	TON	TOWN HIGHWAY APPROACHES
218	TON	ROUNDING
5,000	TON	TOTAL

PROJECT NAME: JOHNSON - HYDE PARK
PROJECT NUMBER: STP SURF(52)
FILE NAME: I4v204\pl4v204.dgn\pl4v204_I3.1
DESIGNED BY: K. LOCKE
QUANTITY SHEET 2
PLOT DATE: 05-NOV-2015
DRAWN BY: K. LOCKE
CHECKED BY: M. FOWLER
SHEET 13 OF 45