QUANTITY SHEET 1

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

ROADWAY ALT. A	ROADWAY ALT. B	BRIDGE	ROADWAY	FULL C.E.	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
			29,500		29,500	LF	SHOULDER BERM REMOVAL	203.40	EST
			1		1	CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	-
			14,810		14,810	LF	MILLED RUMBLE STRIPS (CENTERLINE)	213.10	EST
							BEGIN OPTION AA		
			1,500		1,500	TON	AGGREGATE SHOULDERS	402.12	152
			1,500		1,500	TON	AGGREGATE SHOULDERS, RAP	402.13	152
							END OPTION AA		
			1		1	LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50	-
			15,500		15,500	LB	BITUMINOUS CRACK SEALING, "BLOW AND GO" METHOD (AASHTO M 324 (ASTM D 6690) TYPE II)	417.20	326
		520			520	LF	BRIDGE EXPANSION JOINT, ASPHALTIC PLUG	516.10	6
		250			250	LF	BRIDGE EXPANSION JOINT, ASPHALTIC PLUG (@ FINGER PLATE/VERMONT JOINT)	516.10	6
		50			50	CF	RAPID SETTING CONCRETE REPAIR MATERIAL WITH COARSE AGGREGATE	580.20	EST
			20		20	EA	CHANGING ELEVATION OF DI, CB, OR MH	604.40	-
			100		100	HR	POWER BROOM RENTAL, TYPE I	608.30	EST
			100		100	HR	POWER BROOM RENTAL, TYPE II	608.31	EST
			100		100	HR	TRUCK RENTAL	608.37	EST
			3		3	EA	ADJUST ELEVATION OF VALVE BOX	629.20	-
			450		450	HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST
			2,250		2,250	HR	FLAGGERS	630.15	EST
				0.5	0.5	LS	FIELD OFFICE, ENGINEERS	631.10	-
				0.5	0.5	LS	TESTING EQUIPMENT, BITUMINOUS	631.17	-
				1,500	1,500	DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26	-
			0.5		0.5	LS	MOBILIZATION/DEMOBILIZATION	635.11	-
			1		1	LS	TRAFFIC CONTROL (STP SURF(53))	641.10	-
			5		5	EA	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	EST
							BEGIN OPTION BB		
			360		360	LF	DURABLE 24 INCH STOP BAR, THERMOPLASTIC	646.482	EST
			360		360	LF	SPECIAL PROVISION (DURABLE 24 INCH STOP BAR, POLYUREA) (28 MIL)	900.640	EST
							END OPTION BB		
							BEGIN OPTION CC		
			89		89	EA	DURABLE LETTER OR SYMBOL, THERMOPLASTIC	646.492	-
			89		89	EA	SPECIAL PROVISION (DURABLE LETTER OR SYMBOL, POLYUREA) (28 MIL)	900.620	-
							END OPTION CC		
			155,700		155,700	LF	TEMPORARY 4 INCH WHITE LINE, PAINT	646.602	EST
			145,400		145,400	LF	TEMPORARY 4 INCH YELLOW LINE, PAINT	646.612	EST

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

PROJECT NAME: BELVIDERE - BERKSHIRE
PROJECT NUMBER: STP SURF(53)

FILE NAME: I4v204\pI4v204.dgn\pI4v204_25.I
PROJECT LEADER: M. FOWLER
DESIGNED BY: K. LOCKE
QUANTITY SHEET I

PLOT DATE: 04-NOV-2015
DRAWN BY: K. LOCKE
CHECKED BY: M. FOWLER
SHEET 25 OF 45