

QUANTITY SHEET 2

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
								ROADWAY	48 INCH CULVERT	FULL C.E.	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
								90			90		HR	LOADER RENTAL, TYPE I	608.40	EST.			
								600			600		CY	STONE FILL, TYPE I	613.10	43			
									60		60		CY	STONE FILL, TYPE II	613.11	1			
								135			135		LF	VERTICAL GRANITE CURB	616.21	4			
								25			25		EACH	RELOCATE MAILBOX, SINGLE SUPPORT	617.10	EST.			
								5			5		EACH	RELOCATE MAILBOX, MULTIPLE SUPPORT	617.12	EST.			
								60			60		SY	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	618.10	8			
								20			20		SF	DETECTABLE WARNING SURFACE	618.30				
								211			211		EACH	YIELDING MARKER POSTS	619.17	-			
								4150			4150		LF	STEEL BEAM GUARDRAIL, GALVANIZED	621.20	21.5			
									5		5		EACH	ENERGY ABSORPTION ATTENUATOR	621.56	-			
								56			56		EACH	ANCHOR FOR STEEL BEAM RAIL	621.60	-			
								6925			6925		LF	REMOVE AND RESET GUARDRAIL	621.75	-			
								82			82		EACH	REPLACE GUARDRAIL POST ASSEMBLY	621.76	-			
								120			120		EACH	REPLACE GUARDRAIL BEAM UNIT	621.77	-			
								5240			5240		LF	ADJUST HEIGHT OF GUARDRAIL	621.79	-			
								3927			3927		LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80	-			
									560		560		LF	TEMPORARY TRAFFIC BARRIER	621.90	-			
									544		544		LF	REMOVE AND RESET TEMPORARY TRAFFIC BARRIER	621.95	-			
								1			1		EACH	ADJUST ELEVATION OF VALVE BOX	629.20	-			
								2800			2800		HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST.			
								9800			9800		HR	FLAGGERS	630.15	EST.			
										1	1		LS	FIELD OFFICE, ENGINEERS	631.10	-			
										1	1		LS	TESTING EQUIPMENT, CONCRETE	631.16	-			
										1	1		LS	TESTING EQUIPMENT, BITUMINOUS	631.17	-			
										3000	3000		DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26	-			
								1			1		LS	MOBILIZATION/DEMobilIZATION	635.11	-			
								1			1		LS	TRAFFIC CONTROL	641.10	-			
								8	2		10		EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	-			
														BEGIN OPTION CC					
								208000			208000		LF	DURABLE 4 INCH WHITE LINE, THERMOPLASTIC	646.402	1101			
								208000			208000		LF	DURABLE 4 INCH WHITE LINE, EPOXY PAINT	646.403	1101			
								208000			208000		LF	DURABLE 4 INCH WHITE LINE, POLYUREA	646.404	1101			
														END OPTION CC					
														BEGIN OPTION DD					
								163000			163000		LF	DURABLE 4 INCH YELLOW LINE, EPOXY PAINT	646.413	757			
								163000			163000		LF	DURABLE 4 INCH YELLOW LINE, POLYUREA	646.414	757			
														END OPTION DD					

Sheet has not been updated.
See SiteManager for quantities
utilized on this project.

PROJECT NAME: MIDDLEBURY-STARKSBORO
PROJECT NUMBER: STP 2953(I)

FILE NAME: z14V227quant.dgn
PROJECT LEADER: C.LATHROP
DESIGNED BY: J. GOODALL
QUANTITY SHEET 2

PLOT DATE: 5/4/2017
DRAWN BY: J. GOODALL
CHECKED BY: C.LATHROP
SHEET 14 OF 186