

STATE OF VERMONT
AGENCY OF TRANSPORTATION

ITEM DETAIL SHEET 1

BEGIN STATION	END STATION	POS.	203.30 EARTH BORROW	402.12 OR 402.13 AGGREGATE SHOULDERS (OPTION ITEM)	604.412, 604.415, 604.418 REHAB. DI, CB OR MH CLASS I, II, III	613.10 STONE FILL, TYPE I	619.17 YIELD MARKER POSTS	621.20 STEEL BEAM G.R. GALV	621.60 ANCHOR FOR S.B. G.R.	621.75 REMOVE & RESET G.R.	621.76 REPLACE G.R. POST ASSEMBLY	621.77 REPLACE G.R. BEAM UNIT	621.79 ADJUST HEIGHT OF G.R.	621.80 REMOVE & DISP. OF G.R.	649.51 GEOT. FOR SILT FENCE	651.35 TOPSOIL	651.40 GRUBBING MATERIAL (6")	653.20 TEMP. EROSION MATTING	676.10 DELINE. WITH STEEL POSTS	676.12 REMOVAL OF EXIST. DELINE.	676.15 REMOVE & REPLACE REFLEC. UNIT	REMARKS
			CY	TON	EACH	CY	EACH	LF	EACH	LF	EACH	EACH	LF	LF	SY	CY	SY	SY	EACH	EACH	EACH	
MIDDLEBURY				756		20	89								30	121	40	40				ITEMS FOR USE BY ENGINEER. STONE FILL AND OTHER RELATED ITEMS FOR USE IF ERODED AREAS ARE ENCOUNTERED.
59+44	59+83	LT	50													3	18	67				
59+55	59+93	RT	50													5	16	91				
146+85	148+45	RT	25					37.5	1		1		160	37.5		5		25	2	2	4	GUARDRAIL POSTS AND PANELS PROVIDED FOR USE AT ENGINEERS DISCRETION. SEE VTRANS STD GI-D FOR END SECTION DETAILS
147+35	152+44	LT	50					500	2					500		10		50	2	2		SEE VTRANS STD GI-D FOR END SECTION DETAILS
148+73	150+36	RT	50					162.5	2					162.5		10		50	2	2		SEE VTRANS STD GI-D FOR END SECTION DETAILS
260+89	262+46	LT	25					37.5	1	125				37.5		5		25	2	2	4	GUARDRAIL POSTS AND PANELS PROVIDED FOR USE AT ENGINEERS DISCRETION. SEE VTRANS STD GI-D FOR END SECTION DETAILS
261+00	262+50	LT				55									67							REMOVE EXISTING TIMBER CURB, REPLACE WITH 6FT WIDE STONE FILL, TYPE I APRON
267+48	271+02	LT	50					75	2	275	3	2		75		10		50	2	2	9	GUARDRAIL POSTS AND PANELS PROVIDED FOR USE AT ENGINEERS DISCRETION. SEE VTRANS STD GI-D FOR END SECTION DETAILS
278+16	279+91	LT	50					175	2					175		10		50	2	2		SEE VTRANS STD GI-D FOR END SECTION DETAILS
278+74	279+67	RT	50					100	2					100		10		50	2	2		SEE VTRANS STD GI-D FOR END SECTION DETAILS
281+86	285+65	LT	50					75	2		1	6	300	75		10		50	2	2	8	GUARDRAIL POSTS AND PANELS PROVIDED FOR USE AT ENGINEERS DISCRETION. SEE VTRANS STD GI-D FOR END SECTION DETAILS
293+23	296+89	LT	50					75	2		1		292.5	75		10		50	2	2	10	GUARDRAIL POSTS PROVIDED FOR USE AT ENGINEERS DISCRETION. SEE VTRANS STD GI-D FOR END SECTION DETAILS
301+45	310+73	LT	50					75	2		5	3	850	75		10		50	2	2	27	GUARDRAIL POSTS AND PANELS PROVIDED FOR USE AT ENGINEERS DISCRETION. SEE VTRANS STD GI-D FOR END SECTION DETAILS
309+21		RT																				
330+51	335+04	LT	50					75	2		5	7	375	75		10		50	2	2	10	GUARDRAIL POSTS AND PANELS PROVIDED FOR USE AT ENGINEERS DISCRETION. SEE VTRANS STD GI-D FOR END SECTION DETAILS
BRISTOL				1211		20	106								30	199	40	40				ITEMS FOR USE BY ENGINEER. STONE FILL AND OTHER RELATED ITEMS FOR USE IF ERODED AREAS ARE ENCOUNTERED.
A 21+01	A 23+53	RT	50					75	2		4	2	175	75		10		50	2	2	5	GUARDRAIL POSTS AND PANELS PROVIDED FOR USE AT ENGINEERS DISCRETION. SEE VTRANS STD GI-D FOR END SECTION DETAILS
A 42+93	A 48+30	LT							-		8	3	537.5						2	2	16	GUARDRAIL POSTS AND PANELS PROVIDED FOR USE AT ENGINEERS DISCRETION
A 43+20	A 49+18	RT							-		10	5	600						2	2	18	GUARDRAIL POSTS AND PANELS PROVIDED FOR USE AT ENGINEERS DISCRETION
A 103+33	A 104+57	RT														18			12			REMOVE PULLOFF
A 143+08	A 144+35	RT														20			13			REMOVE PULLOFF
A 177+82	A 181+85	RT	50					400	2					354		10		50	2	2		SEE VTRANS STD GI-D FOR END SECTION DETAILS
A 178+25	A 181+00	RT				96																REMOVE EXISTING TIMBER CURB, REPLACE WITH 6FT WIDE STONE FILL, TYPE I APRON
TOTAL			700	1967	1	191	195	1862.5	24	400	38	28	3290	1816.5	249	486	114	838	55	30	111	

Sheet has not been updated.
See SiteManager / E-Books for locations and quantities utilized on this project.

PROJECT NAME: MIDDLEBURY-STARKSBORO
PROJECT NUMBER: STP 2953(I)
FILE NAME: z14V2271ds.dgn PLOT DATE: 5/4/2017
PROJECT LEADER: C.LATHROP DRAWN BY: J.GOODALL
DESIGNED BY: J.GOODALL CHECKED BY: C.LATHROP
ITEM DETAIL SHEET 1 SHEET 17 OF 186