

INDEX OF SHEETS

INDEX OF SHEETS

1. TITLE SHEET
2. INDEX OF SHEETS
3. CONVENTIONAL SYMBOLOGY LEGEND SHEET
4. PROJECT NOTES
5. TYPICAL SECTIONS SHEET
- 6.-8. DETAIL SHEETS (1-3)
- 9.-10. QUANTITY SHEETS (1-2)
- 11.-30. PLAN SHEETS (1-20)
31. BANKING SHEET
32. TRAFFIC CONTROL NOTES
33. CONSTRUCTION APPROACH SIGNING SHEET

STRUCTURES DETAIL SHEETS

SD-516.10 - BRIDGE JOINT ASPHALTIC PLUG

HIGHWAY SAFETY AND DESIGN DETAIL SHEETS

HSD - 400.01 - SAFETY EDGE DETAILS

TRAFFIC DATA

VT ROUTE 12	AADT		DHV		%T		%D		ADTT		ESALs	
	2015	2025	2015	2025	2015	2025	2015	2025	2015	2025	(2015~2025)	(2015~2025)
MM 3.946 (ELMORE) - MM 3.520 (WORCESTER)	1000	1000	140	140	1.5	1.9	58	58	45	55	124,000	302,000

POSTED SPEED ZONES

VT ROUTE 12	TOWN	SPEED (MPH)
MM 3.946 - MM 7.853	WORCESTER	50
MM 0.000 - MM 3.520	ELMORE	50

BITUMINOUS CONCRETE PAVEMENT SUPERPAVE MIXTURE DESIGN CRITERIA	
DESIGN LANE / DESIGN LIFE ESAL	175,160
DESIGN NUMBER OF GYRATIONS	65
PERFORMANCE GRADE ASPHALT BINDER	58-34

VAOT DESIGN STANDARDS

E-170	11-04-99
E-171A	08-09-95
E-171B	08-09-95
E-173	08-09-95
E-190	06-30-03
E-191	02-01-99
E-192	10-12-00
E-193	08-18-95
T-1	04-25-16
T-10	08-06-12
T-11	08-06-12
T-13	08-06-12
T-17	08-06-12
T-24	08-06-12
T-28	08-06-12
T-29	08-06-12
T-30	08-06-12
T-31	08-06-12
T-36	08-06-12

PROJECT NAME: WORCESTER-ELMORE

PROJECT NUMBER: STP 2954(I)

FILE NAME: pl4v23lwrk.dgn

PROJECT LEADER: J. HARRINGTON

DESIGNED BY: B. KIPP

INDEX OF SHEETS

PLOT DATE: 13-MAY-2016

DRAWN BY: B. KIPP

CHECKED BY: N. PAPPAS

SHEET 2 OF 33