

# QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
								EROSION CONTROL	ROADWAY	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
									7		7		EACH	REMOVING MEDIUM TREES	201.15	-			
									7		7		EACH	REMOVING MEDIUM STUMPS	201.20	-			
									1725		1725		CY	COMMON EXCAVATION	203.15	40			
									1		1		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	-			
									4		4		CWT	EMULSIFIED ASPHALT	404.65	1			
									1		1		LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50	-			
									20		20		HR	POWER BROOM RENTAL, TYPE I	608.30	EST			
									1150		1150		CY	STONE FILL, TYPE II	613.11	17			
									400		400		HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST			
									400		400		HR	FLAGGERS	630.15	EST			
										1	1		LS	TESTING EQUIPMENT, BITUMINOUS	631.17	-			
									1		1		LS	MOBILIZATION/DEMOBILIZATION	635.11	-			
									1		1		LS	TRAFFIC CONTROL	641.10	-			
									2		2		EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	-			
									2500		2500		SY	GEOTEXTILE UNDER STONE FILL	649.31	133			
								350			350		SY	GEOTEXTILE FOR SILT FENCE	649.51	17			
								450			450		LB	SEED	651.15	28			
								1780			1780		LB	FERTILIZER	651.18	20			
								3			3		TON	AGRICULTURAL LIMESTONE	651.20	1			
								3			3		TON	HAY MULCH	651.25	1			
									150		150		CY	TOPSOIL	651.35	8			
								2100			2100		SY	TEMPORARY EROSION MATTING	653.20	88			
								7			7		CY	VEHICLE TRACKING PAD	653.35	2			
								1000			1000		LF	PROJECT DEMARCATION FENCE	653.55	70			
									1		1		EACH	REMOVING SIGNS	675.50	-			
									1		1		EACH	ERECTING SALVAGED SIGNS	675.60	-			
									1		1		EACH	SETTING SALVAGED POSTS	675.61	-			
									20		20		EACH	DELINEATOR WITH STEEL POST	676.10	-			
									450		450		CY	SPECIAL PROVISION (GABION MATTRESS)	900.608	25			
									1		1		LU	SPECIAL PROVISION (MIXTURE PAY ADJUSTMENT)(N.A.B.I.)	900.650	-			
									65		65		TON	SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT, SMALL QUANTITY)	900.680	-			

PROJECT NAME: ESSEX  
PROJECT NUMBER: STP 2912(2)  
FILE NAME: p14v256\_details.dgn  
PROJECT LEADER: M. FOWLER  
DESIGNED BY: N. PAPPAS  
QUANTITY SHEET

PLOT DATE: 08-JUN-2015  
DRAWN BY: N. PAPPAS  
CHECKED BY: M. FOWLER  
SHEET 6 OF 17