



CLEARING LIMITS FOR SIGNS ON CONVENTIONAL ROADS

SIGN LOCATIONS:
VT ROUTE 15
SEE SIGN SUMMARY SHEETS
FOR THINNING AND TRIMMING LOCATIONS

MINIMUM SIGN SIGHT DISTANCE CHART

APPROACH SPEED (mph)	SIGHT DISTANCE (feet)
30 OR LESS	300
35	350
40	400
45	450
50	500
55	550

THE CONTRACTOR SHALL REMOVE ALL WOODY STEMMED GROWTH INCLUDING BRUSH, SAPPLINGS, TREE LIMBS GROWING WITHIN OR PROJECTING INTO THE CLEARANCE AREA AND DOWN TO GROUND LEVEL OR AT LEAST 10 FEET BELOW THE BOTTOM OF THE SIGN. PAYMENT PER ITEM 201.31 THINNING AND TRIMMING FOR SIGNS. NO CHEMICALS (POISONS OR DEFOLIANTS) ALLOWED.

NOT TO SCALE

PROJECT NAME: WINOOSKI-CAMBRIDGE
PROJECT NUMBER: STPG SIGN(55)

FILE NAME: z15+006+yp.dgn	PLOT DATE: 6/14/2016
PROJECT LEADER: M. FOISY	DRAWN BY: D. DRAPER
DESIGNED BY: G. BARRETT	CHECKED BY: M. FOISY
TRAFFIC SIGN DETAILS SHEET 3	SHEET 6 OF 192

