DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
WINOOSKI VT-15 EB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
EB	0.060	A	R2-1	24	30		SPEED LIMIT 25						1		X													
		A	UNK.	12	18		CCTA BUS STOP				1		1															
		A	R2-1	24	30			5.00								1		X							USE EXISTING SLEEVE	X		
		A	UNK.	12	18		CCTA BUS STOP					1																
EB	0.070	A	W11-2	30	30		PEDESTRIAN						1		X													
		A	W16-7P	21	15		DIAGONAL ARROW						1															
		A	W11-2	30	30	FYG		6.25								1		X							USE EXISTING SLEEVE	X		
		A	W16-7P	24	12	FYG		2.00																		X		
EB	0.070	C	W11-2	30	30	FYG		6.25								1		X							CASCADE WAY (TH-7) INSTALL ON SLIP RAMP	X		
		C	W16-7P	24	12	FYG		2.00																	SLEEVE TO BE INSTALLED IN EXISTING BRICK PAVERS PER VAOT STANDARD T-45	X		
EB	0.078	C	VR-017	24	30		LLL 24,000 LBS						1		X										CASCADE WAY (TH-7) REMOVE SIGN AND RETURN TO CITY			
EB	0.079	B	R3-2	24	24		NO LEFT TURN						1												CASCADE WAY (TH-7): MOUNT NEW SIGN ON EXISTING LIGHT POLE USING STAINLESS STEEL BANDS (INCIDENTAL)			
		B	R3-2	24	24			4.00																		X		
SIGN SUMMARY SHEET							SHEET TOTALS	25.50	0.00	0	1	1	6	0	0	3		45.0		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	443.72	0.0	15	2	2	97	0	0	34		510.0		2		198.0							

PROJECT NAME: **WINOOSKI-CAMBRIDGE**
PROJECT NUMBER: **STPG SIGN(55)**
FILE NAME: **WINOOSKI VT15 EB TSS.xls** PLOT DATE: **6/14/2016**
PROJECT MANAGER: **M. FOISY** DRAWN BY: **D. DRAPER**
DESIGNED BY: **D. DRAPER** CHECKED **M. FOISY**
WINOOSKI EB SHEET 2 SHEET **21** OF **192**