DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
WINOOSKI VT-15 WB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
WB	0.758	F	R10-7	24	30		DO NOT BLOCK INTERSECTION			1				X														
WB	0.755	F	D3-1	30	6		FLORIDA AVE						1		X											FLORIDA AVE		
		G	D3-1	30	6		E ALLEN ST						1													FLORIDA AVE		
WB	0.749	H	R1-1	30	30		STOP						1		X											FLORIDA AVE		
		F	D3-1	30	8		Florida Ave	1.67								1		X								FLORIDA AVE		7
		G	D3-1	30	8		E Allen St	1.67																		FLORIDA AVE		7
		H	R1-1	30	30		STOP	6.25																		FLORIDA AVE	X	
WB	0.735	F	M3-4	24	12		WEST			1				X														
		F	M1-5	24	24		VERMONT 15			1																		
WB	0.725	F	R10-7	24	30		DO NOT BLOCK INTERSECTION						1		X													
		F	UNK.	30	30		YOU CAN'T AFFORD IT				1		1															
		F	R10-7	24	30		DO NOT BLOCK INTERSECTION	5.00								1		X									X	
		F	UNK.	30	30		YOU CAN'T AFFORD IT					1																
WB	0.690	F	UNK.	18	24		DO NOT BLOCK DRIVEWAY						1		X													
		F	R10-7	24	30		DO NOT BLOCK INTERSECTION	5.00								1		X								INSTALL AWAY FROM TREE FOR IMPROVED VISIBILITY	X	
							SHEET TOTALS	19.59	0.00	3	1	1	6	0	0	3		45.0		0	0.0	0.0	0.0	0.0			
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB			
							TOWN DIRECTIONAL TOTALS	282.75	0.0	29	15	15	98	0	0	30		450.0		1	118.0						

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **WINOOSKI-CAMBRIDGE**
PROJECT NUMBER: **STPG SIGN(55)**

FILE NAME: **WINOOSKI VT15 WB TSS.xls** PLOT DATE: **6/14/2016**
PROJECT MANAGER: **M. FOISY** DRAWN BY: **D. DRAPER**
DESIGNED BY: **D. DRAPER** CHECKED **M. FOISY**
WINOOSKI WB SHEET 1 SHEET **35** OF **192**