DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
WINOOSKI VT-15 WB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
		F	W16-7P	24	12		DIAGONAL ARROW						1																
		F	UNK.	24	18		VT DIVISION III GIRLS BASKETBALL CHAMPIONS						1														REMOVE SIGN AND RETURN TO CITY			
		F	W11-2	36	36	FYG		9.00								1		X									X		
		F	W16-7P	24	12	FYG		2.00																			X		
WB	0.565	F	D3-1	24	6		DION ST						1														DION ST (TH-5)			
		G	D3-1	24	6		E ALLEN ST						1														DION ST (TH-5)			
		F	D3-1	24	8			1.33																		DION ST (TH-5); MOUNT NEW ST. SIGNS ON EXISTING LIGHT POLE USING STAINLESS STEEL BANDS (INCIDENTAL)		7	
		G	D3-1	30	8			1.67																				7	
WB	0.560	H	R1-1	30	30		STOP			1				X															
WB	0.535	F	R8-3	12	12		NO PARKING						1		X												THINNING AND TRIMMING NEEDED			
		F	UNK.	12	18		BUS STOP				1		1																
		F	R8-3	24	24			4.00									1		X								INSTALLED PER ADDENDUM TO CHAPTER 21 OF PARKING ORDINANCES	X		
		F	UNK.	12	18		BUS STOP					1																	
WB	0.520	F	VR-921R	30	30		THRU/RIGHT "ONLY"						1		X															
		F	VR-921R	30	30			6.25								1		X											E-145A
SIGN SUMMARY SHEET							SHEET TOTALS	24.25	0.00	1	1	1	7	0	0	3		45.0		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	282.75	0.0	29	15	15	98	0	0	30		450.0		1	118.0								

PROJECT NAME: **WINOOSKI-CAMBRIDGE**
PROJECT NUMBER: **STPG SIGN(55)**

FILE NAME: **WINOOSKI VT15 WB TSS.xls** PLOT DATE: **6/14/2016**
PROJECT MANAGER: **M. FOISY** DRAWN BY: **D. DRAPER**
DESIGNED BY: **D. DRAPER** CHECKED **M. FOISY**
WINOOSKI WB SHEET 5 SHEET **39** OF **192**