| DIRECTION | MILEPOINT | LOCATION CODE (SHEET 2) | SIGN CODE | WIDTH (IN) | HEIGHT (IN) | SHEETING REMARKS | SIGN LEGEND | NEW SIGNS | | EXISTING SIGNS | | | | EXIST POST | | NUMBER OF NEW POSTS | SQUARE STEEL (IN) | | | TUBULAR STEEL Ø (IN) | | | | SIGN FRAME REQUIRED | REMARKS | SIGN DETAIL LOCATION | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | | "A" | "B" | RETAIN | SALVAGE FROM | SALVAGE TO | REMOVE | RETAIN | REMOVE | | 1.75 (LB / FT) 1.88 | 2.00 (LB / FT) 2.42 | 2.50 (LB / FT) 3.35 | FOUNDATION | 3.00 (LB / FT) 7.60 | 3.50 (LB / FT) 9.00 | 4.00 (LB / FT) 10.80 | 5.00 (LB / FT) 14.60 | | | SHSM | PROJECT SHEET # | STANDARD SHEET # |
| **WINOOSKI VT-15 WB** | | | | | | | FY-FLUORESCENT YELLOW<br>FYG-FLUORESCENT YELLOW GREEN | | | | | | | | | | | | | | | | | | "SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS | | | |
| WB | 0.050 | F | UNK. | 12 | 18 | | CAUTION ROTARY AHEAD | | | | | | 1 | | X | | | | | | | | | | | | | |
| | | F | W13-1P | 18 | 18 | | 25 MPH | | | | 1 | | 1 | | | | | | | | | | | | SALVAGE TO SAME LOCATION | | | |
| | | F | W2-6 | 30 | 30 | | | 6.25 | | | | | | | | 1 | | X | | | | | | | | X | | |
| | | F | W3-2 | 30 | 30 | | | 6.25 | | | | | | | | | | | | | | | | | X | | |
| | | F | W13-1P | 18 | 18 | | 25 MPH | | | | | 1 | | | | | | | | | | | | | | | | |
| WB | 0.048 | F | R3-17 | 24 | 18 | | | 3.00 | | | | | | | | | | | | | | | | | MOUNT NEW SIGN ON EXISTING LIGHT POLE USING STAINLESS STEEL BANDS (INCIDENTAL) | X | | |
| | | F | R3-17bP | 24 | 8 | | | 1.33 | | | | | | | | | | | | | | | | | | X | | |
| WB | 0.042 | F | UNK. | 24 | 30 | | BIKE LANE ENDS | | | | | | 1 | | X | | | | | | | | | | | | | |
| WB | 0.040 | G | UNK. | 12 | 18 | | WINOOSKI PAY FOR PARKING | | | | | | 1 | X | | | | | | | | | | | REMOVE SIGN AND RETURN TO CITY | | | |
| | | G | UNK. | 12 | 18 | | PAY AT KIOSK | | | | | | 1 | | | | | | | | | | | | REMOVE SIGN AND RETURN TO CITY | | | |
| | | G | UNK. | 12 | 6 | | LEFT ARROW | | | | | | 1 | | | | | | | | | | | | REMOVE SIGN AND RETURN TO CITY | | | |
| | | G | UNK. | 12 | 6 | | ADDITIONAL PARKING IN GARAGE | | | | 1 | | 1 | | | | | | | | | | | | | | | |
| | | G | R7-108 | 12 | 18 | | | 1.50 | | | | | | | | | | | | | | | | | INSTALLED PER ADDENDUM TO CHAPTER 21 OF PARKING ORDINANCES | X | | |
| | | G | UNK. | 12 | 6 | | ADDITIONAL PARKING IN GARAGE | | | | | 1 | | | | | | | | | | | | | | | | |
| WB | 0.030 | F | N/A | | | | EMPTY POST | | | | | | | | X | | | | | | | | | | REMOVE EMPTY POST AND KEEP EXISTING SLEEVE | | | |
| | | | | | | | SHEET TOTALS | 18.33 | 0.00 | 0 | 2 | 2 | 7 | 0 | 0 | 1 | 15.0 | | | 0 | 0.0 | 0.0 | 0.0 | 0.0 | | | | |
| | | | | | | | | SF | SF | EA | EA | EA | EA | EA | EA | EA | FT | | | EA | LB | LB | LB | LB | | | | |
| | | | | | | | TOWN DIRECTIONAL TOTALS | 282.75 | 0.0 | 29 | 15 | 15 | 98 | 0 | 0 | 30 | 450.0 | | | 1 | 118.0 | | | | | | | |

# SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **WINOOSKI-CAMBRIDGE**
PROJECT NUMBER: **STPG SIGN(55)**

FILE NAME: **WINOOSKI VT15 WB TSS.xls** PLOT DATE: **6/14/2016**
PROJECT MANAGER: **M. FOISY** DRAWN BY: **D. DRAPER**
DESIGNED BY: **D. DRAPER** CHECKED **M. FOISY**
WINOOSKI WB SHEET 13 SHEET **47** OF **192**