DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
COLCHESTER VT-15 WB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
WB	0.758	F	D3-1	36	9		JOHNSON AVE						1		X											JOHNSON AVE (TH-9)			
WB	0.758	H	R1-1	30	30		STOP						1	X												JOHNSON AVE (TH-9)			
		F	D3-1	42	12		Johnson Ave	3.50																		JOHNSON AVE (TH-9)		8	
		G	D3-1	42	12		VT Route 15	3.50																		JOHNSON AVE (TH-9)		12	
		H	R1-1	36	36		STOP	9.00																		JOHNSON AVE (TH-9)	X		
WB	0.708	F	W1-8	18	24			3.00								1		X								INSTALL 10 FEET EAST OF UTILITY POLE # 89703	X		
WB	0.703	F	W1-8	18	24		CHEVRON						1		X														
WB	0.693	F	R2-1	24	30		SPEED LIMIT 35						1	X															
		F	W1-8	18	24			3.00																			X		
WB	0.673	F	W1-8	18	24		CHEVRON						1	X															
		F	W1-8	18	24			3.00																			X		
WB	0.635	F	R2-1	30	36			7.50								1		X								INSTALL 200 FEET WEST OF CHEVRON AT MM 0.673	X		
WB	0.593	F	R2-1	24	30		SPEED LIMIT 35						1		X														
WB	0.508	F	W3-3	36	36		SIGNAL AHEAD				1		1		X														
		F	W16-8P	30	8		LIME KILN RD						1													REPLACE EXISTING FLASHING BEACON SIGNAL HEAD WITH NEW LED FLASHING BEACON SIGNAL			
							SHEET TOTALS	32.50	0.00	0	1	0	8	0	0	2		30.0		0	0.0	0.0	0.0	0.0				
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB				
							TOWN DIRECTIONAL TOTALS	245.92	26.0	13	8	8	43	0	0	35		525.0		0	0.0							

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **WINOOSKI - CAMBRIDGE**
PROJECT NUMBER: **STPG SIGN(55)**

FILE NAME: **COLCHESTER VT 15 WB TSS.** PLOT DATE: **6/14/2016**
PROJECT MANAGER: **M. FOISY** DRAWN BY: **G. BARRETT**
DESIGNED BY: **G. BARRETT** CHECKED **M. FOISY**
COLCHESTER WB SHEET 5 SHEET **71** OF **192**