DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
COLCHESTER VT-15 WB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
		F	W3-3	36	36		SIGNAL AHEAD					1				2		X								HEAD. SPECIAL PROVISION (FLASHING BEACON SIGNAL HEADS, LED).			
		F	W16-8P	36	10			2.50																				17	
WB	0.478	F	VW1-2M	36	36		MODIFIED CURVE ARROW RIGHT						1		X														
		F	W1-10	36	36			9.00								2		X							THINNING AND TRIMMING NEEDED	X		
WB	0.458	F	VR-934L	48	30		LEFT "ONLY"/THRU/THRU & RIGHT						1		X														
		F	VR-934L	48	30			10.00								2		X											E-145B
WB	0.276	F	W11-8	30	30		FIRE STATION						1		X														
		F	W11-8	36	36			9.00								2		X									X		
WB	0.239	F	VR-934L	48	30		LEFT "ONLY"/THRU/THRU & RIGHT						1		X														
		F	VR-934L	48	30			10.00								2		X											E-145B
WB	0.198	F	R2-1	24	30		SPEED LIMIT 35						1	X															
		F	R2-1	30	36			7.50																				X		
WB	0.131	F	W3-5	36	36		REDUCE SPEED LIMIT 25 AHEAD						1	X															
		F	W3-5	36	36			9.00																				X		
WB	0.056	F	W3-3	36	36		SIGNAL AHEAD				1		1		X														
SIGN SUMMARY SHEET							SHEET TOTALS	57.00	0.00	0	1	1	7	0	0	10		150.0		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	245.92	26.0	13	8	8	43	0	0	35		525.0		0	0.0								

PROJECT NAME: **WINOOSKI - CAMBRIDGE**
PROJECT NUMBER: **STPG SIGN(55)**

FILE NAME: **COLCHESTER VT 15 WB TSS.** PLOT DATE: **6/14/2016**
PROJECT MANAGER: **M. FOISY** DRAWN BY: **G. BARRETT**
DESIGNED BY: **G. BARRETT** CHECKED **M. FOISY**
COLCHESTER WB SHEET 6 SHEET **72** OF **192**