DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB/FT) 1.88	SQUARE STEEL (IN) 2.00 (LB/FT) 2.42	SQUARE STEEL (IN) 2.50 (LB/FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB/FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB/FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB/FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB/FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
ESSEX VT-15 EB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																				"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
		A	R9-6	12	18		YIELD TO PEDESTRIANS						1																
		A	R5-3	24	24			4.00								1		X								SHARED USE PATH	X		
		A	R9-6	12	18			1.50																		SHARED USE PATH	X		
EB	4.452	A	VD-062B	72	16		BUSINESS SIGN-O'LEARY-BURKE ^UP / ALLEN MARTIN DR. 2-3/10			1				X															
		A	VD-062B	72	16		BUSINESS SIGN-MORSE HILLSIDE FARM ^UP / 128 TO OSGOOD HILL 6			1																			
		A	VD-062B	72	16		BUSINESS SIGN-SAXON HILL STORAGE ^UP / A. MARTIN TO CORP DR 2-1/10			1																			
EB	4.512	A	VD-062AL	72	16		BUSINESS SIGN-CHAPIN <=== / ORCHARD 1-5/10			1				X															
		A	VD-062B	72	16		BUSINESS SIGN-SANDY PINES <=== / BOARDING KENNEL 2			1																			
EB	4.528	A	VR-921R	30	30		STRAIGHT/RIGHT ONLY						1		X														
EB	4.557	A	VR-921R	30	30			6.25																		INSTALL AT BEGINNING OF SOLID WHITE LINE FOR TURNING LANE			E-145A
EB	4.560	C	R5-3	24	24		NO MOTOR VEHICLES						1		X														
		C	R9-6	12	18		YIELD TO PEDESTRIANS						1																
		C	R5-3	24	24			4.00								1		X									X		
		C	R9-6	12	18			1.50																			X		
EB	4.565	B	D11-1	24	18		BIKE ROUTE						1		X														
							SHEET TOTALS	17.25	0.00	5	0	0	5	0	0	2		30.0		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
							TOWN DIRECTIONAL TOTALS	853.87	0.0	34	20	20	202	0	0	104		1560.0		0	0.0								

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **WINOOSKI - CAMBRIDGE**
PROJECT NUMBER: **STPG SIGN(55)**

FILE NAME: **ESSEX VT15 EB TSS.xls**
PROJECT MANAGER: **M. FOISY**
DESIGNED BY: **G. BARRETT**
ESSEX EB SHEET 16

PLOT DATE: **6/14/2016**
DRAWN BY: **G. BARRETT**
CHECKED **M. FOISY**
SHEET **89** OF **192**