DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
ESSEX VT-15 WB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
WB	8.007	F	W1-2L	30	30		CURVE LEFT						1		X														
		F	W13-1P	18	18		40 MPH						1																
		F	W1-2L	30	30			6.25								1		X									X		
		F	W13-1P	18	18			2.25																			X		
WB	7.919	G	VR-017	24	30		LLL 24,000						1		X												WEED RD (TH-63)			
		G	VR-501	24	30		NO THRU TRUCKS						1														WEED RD (TH-63); REMOVE SIGN AND RETURN TO TOWN			
		G	VR-017	24	30			5.00								1		X										WEED RD (TH-63)			T-70
WB	7.909	H	R1-1	30	30		STOP						1	X													WEED RD (TH-63)			
		F	D3-1	36	12			3.00																			WEED RD (TH-63)		10	
		G	D3-1	42	12			3.50																			WEED RD (TH-63)		12	
		H	R1-1	36	36			9.00																			WEED RD (TH-63)	X		
WB	7.617	F	W11-7	30	30		EQUESTRIAN						1		X														
		F	W11-7	30	30			6.25								1		X									THINNING AND TRIMMING NEEDED	X		
WB	7.442	G	VR-017	24	30		LLL 24,000						1		X												NAYLOR RD (TH-65)			
		G	VR-017	24	30			5.00								1		X									NAYLOR RD (TH-65); THINNING AND TRIMMING NEEDED			T-70
SIGN SUMMARY SHEET							SHEET TOTALS	40.25	0.00	0	0	0	7	0	0	4		60.0		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	650.50	0.0	32	8	8	144	0	0	86		1290.0		0		0.0							

PROJECT NAME: **WINOOSKI - CAMBRIDGE**
PROJECT NUMBER: **STPG SIGN(55)**

FILE NAME: **ESSEX VT15 WB TSS.xls**
PROJECT MANAGER: **M. FOISY**
DESIGNED BY: **G. BARRETT**
ESSEX WB SHEET 1

PLOT DATE: **6/14/2016**
DRAWN BY: **G. BARRETT**
CHECKED **M. FOISY**
SHEET **105** OF **192**