DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
JERICHO VT-15 EB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
		A	VD-700	6	10		MILE MARKER 0260				1		1																
		A	W1-10L	36	36			9.00								2		X										18	
		A	W16-8aP	30	15			3.13																				18	
		A	VD-700	6	10							1																	
EB	2.663	A	D1-1a	72	20		MT MANSFIELD UNION HS 2						1		X														
		A	VD2-1S	72	20			10.00								2		X										T-93	
EB	2.713	A	D3-1	48	12		BROWNS TRACE RD				1		1		X												BROWNS TRACE RD (TH-1) SALVAGE TO MM 2.718			
EB	2.713	C	VR-017	24	30		LLL 24,000						1		X												BROWNS TRACE RD (TH-1); REMOVE SIGN AND RETURN TO TOWN			
		C	UNK.	18	6		TOWN OVERWEIGHT PERMIT REQUIRED						1														BROWNS TRACE RD (TH-1); REMOVE SIGN AND RETURN TO TOWN			
EB	2.718	D	R1-1	30	30		STOP						1		X												BROWNS TRACE RD (TH-1)			
		C	VD-700	6	10		MILE MARKER 0271				1		1														BROWNS TRACE RD (TH-1)			
		A	D3-1	48	12		BROWNS TRACE RD					1				1		X									BROWNS TRACE RD (TH-1) SALVAGE FROM MM 2.713			
		C	D3-1	42	12			3.50																			BROWNS TRACE RD (TH-1)		12	
		D	R1-1	36	36			9.00																			BROWNS TRACE RD (TH-1)	X		
		C	VD-700	6	10							1															BROWNS TRACE RD (TH-1)			
SIGN SUMMARY SHEET							SHEET TOTALS	34.63	0.00	0	3	3	7	0	0	5		75.0		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	408.91	0.0	24	14	14	96	0	0	33		495.0		0	0.0								

PROJECT NAME: **WINOOSKI - CAMBRIDGE**
PROJECT NUMBER: **STPG SIGN(55)**

FILE NAME: **JERICHO VT15 EB TSS.xls** PLOT DATE: **6/14/2016**
PROJECT MANAGER: **M. FOISY** DRAWN BY: **G. BARRETT**
DESIGNED BY: **G. BARRETT** CHECKED **M. FOISY**
JERICHO EB SHEET 10 SHEET **137** OF **192**