DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB/FT) 1.88	SQUARE STEEL (IN) 2.00 (LB/FT) 2.42	SQUARE STEEL (IN) 2.50 (LB/FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB/FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB/FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB/FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB/FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
JERICHO VT-15 WB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																				"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
		E	R10-25	6	8		PED PUSH BUTTON			1																			
WB	0.799	G	R2-2	24	30		SPEED LIMIT 30						1		X												OLD PUMP RD (TH-17); REMOVE SIGN AND RETURN TO TOWN			
WB	0.799	G	VR-017	24	30		LLL 24,000						1		X												OLD PUMP RD (TH-17); REMOVE SIGN AND RETURN TO TOWN			
		G	VR-501	24	24		NO THRU TRUCKS						1														OLD PUMP RD (TH-17); REMOVE SIGN AND RETURN TO TOWN			
WB	0.798	F	D3-1	42	12		OLD PUMP RD						1	X													OLD PUMP RD (TH-17)			
		H	R1-1	30	30		STOP						1														OLD PUMP RD (TH-17)			
		G	VD-700	6	10		MILE MARKER 0081				1		1														OLD PUMP RD (TH-17)			
		F	D3-1	42	12		Old Pump Rd	3.50																			OLD PUMP RD (TH-17)	X	10	
		G	D3-1	42	12		VT Route 15	3.50																			OLD PUMP RD (TH-17)		12	
		H	R1-1	30	30		STOP	6.25																			OLD PUMP RD (TH-17)	X		
		G	VD-700	6	10		0150 0409 0081					1															OLD PUMP RD (TH-17)			
WB	0.748	F	S5-2	24	30		END SCHOOL ZONE						1	X																
		F	R2-1	24	30		SPEED LIMIT 35						1																	
		F	R2-1	24	30		SPEED LIMIT 35	5.00																				X		
		F	S5-2	24	30		END SCHOOL ZONE	5.00																				X		
							SHEET TOTALS	23.25	0.00	1	1	1	8	0	0	0		0.0		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
							TOWN DIRECTIONAL TOTALS	376.57	0.0	12	16	16	94	0	0	27		405.0		0	0.0								

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: WINOOSKI - CAMBRIDGE
PROJECT NUMBER: STPG SIGN(55)

FILE NAME: JERICHO VT15 WB TSS.xls
PROJECT MANAGER: M. FOISY
DESIGNED BY: G. BARRETT
JERICHO WB SHEET 9

PLOT DATE: 6/14/2016
DRAWN BY: G. BARRETT
CHECKED M. FOISY
SHEET 151 OF 192