DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB/FT) 1.88	SQUARE STEEL (IN) 2.00 (LB/FT) 2.42	SQUARE STEEL (IN) 2.50 (LB/FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB/FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB/FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB/FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB/FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
UNDERHILL VT-15 EB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
EB	0.000	C	VD-024	72	10		UNDERHILL/JERICHO						1	X															
		C	VD-700	6	10		MILE MARKER 0000						1																
		C	VD-700	6	10		MILE MARKER 0379						1																
		C	VD-024	72	10		Underhill | Jericho	5.00																					T-94
		C	VD-700	6	10		0150 0415 0000 / 0150 0409 0379	0.42																			INSTALL ON LEFT POST			T-44
		C	VD-700	6	10			0.42																			INSTALL ON RIGHT POST			T-44
EB	0.008	C	VR-017	24	30		LLL 24,000 LBS						1		X												PARK STREET (TH-1)			
		C	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS	5.00								1		X									PARK STREET (TH-1)			T-70
EB	0.008	A	D3-1	18	6		PARK ST						1		X												PARK STREET (TH-1)			
		A	D3-1	30	12		Park St	2.50								1		X									PARK STREET (TH-1)		10	
		C	D3-1	42	12		VT Route 15	3.50																			PARK STREET (TH-1)		12	
EB	0.020	A	R1-1	30	30		STOP						1		X												PARK STREET (TH-1)			
		B	VD-700	6	10		MILE MARKER 0004				1		1														PARK STREET (TH-1)			
		D	R1-1	30	30		STOP	6.25								1		X									PARK STREET (TH-1)	X		
		C	VD-700	6	10		0150 0415 0004					1															PARK STREET (TH-1)			
SIGN SUMMARY SHEET							SHEET TOTALS	23.09	0.00	0	1	1	7	0	0	3		45.0		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	228.41	0.0	3	9	9	53	0	0	27		405.0		0	0.0								

PROJECT NAME: WINOOSKI-CAMBRIDGE
PROJECT NUMBER: STPG SIGN(55)
FILE NAME: UNDERHILL VT15 EB TSS.xls
PROJECT MANAGER: M. FOISY
DESIGNED BY: G. BARRETT
UNDERHILL EB SHEET 1
PLOT DATE: 6/14/2016
DRAWN BY: G. BARRETT
CHECKED M. FOISY
SHEET 157 OF 192