DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
UNDERHILL VT-15 EB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
EB	0.380	D	R1-1	30	30		STOP						1		X											MEADOW LN (TH-52)			
		C	VD-700	6	10		MILE MARKER 0039				1		1													MEADOW LN (TH-52)			
		A	D3-1	42	12		Meadow Ln	3.50								1		X								MEADOW LN (TH-52)		10	
		C	D3-1	42	12		VT Route 15	3.50																		MEADOW LN (TH-52)		12	
		D	R1-1	30	30		STOP	6.25																		MEADOW LN (TH-52)	X		
		C	VD-700	6	10		0150 0415 0039					1														MEADOW LN (TH-52)			
EB	0.455	A	VR-017	24	30		LLL 24,000 LBS						1		X											DUMAS RD (TH-51)			
		C	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS	5.00								1		X								DUMAS RD (TH-51)			T-70
EB	0.455	A	W14-2	30	30		NO OUTLET			1				X												DUMAS RD (TH-51) REMOVE AND RETURN TO TOWN			
EB	0.455	C	D3-1	24	6		DUMAS RD						1		X											DUMAS RD (TH-51)			
EB	0.455	D	R1-1	30	30		STOP						1		X											DUMAS RD (TH-51)			
		C	VD-700	6	10		MILE MARKER 0045				1		1													DUMAS RD (TH-51)			
		A	D3-1	36	12		Dumas Rd VT Route 15	3.00								1		X								DUMAS RD (TH-51)		10	
		C	D3-1	42	12		STOP	3.50																		DUMAS RD (TH-51)		12	
		D	R1-1	30	30		0150 0415 0045	6.25																		DUMAS RD (TH-51)	X		
SIGN SUMMARY SHEET							SHEET TOTALS	31.00	0.00	1	2	1	6	0	0	3		45.0		0	0.0	0.0	0.0	0.0				
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB				
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	228.41	0.0	3	9	9	53	0	0	27		405.0		0	0.0							

PROJECT NAME: WINOOSKI-CAMBRIDGE
PROJECT NUMBER: STPG SIGN(55)
FILE NAME: UNDERHILL VT15 EB TSS.xls
PROJECT MANAGER: M. FOISY
DESIGNED BY: G. BARRETT
UNDERHILL EB SHEET 3
PLOT DATE: 6/14/2016
DRAWN BY: G. BARRETT
CHECKED M. FOISY
SHEET 159 OF 192