DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
UNDERHILL VT-15 EB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
		A	W1-4R	30	30			6.25																			X		
EB	4.664	A	VW-133L	30	30		HIDDEN DRIVE LEFT						1		X														
EB	4.729	A	S3-1	36	36	FYG	SCHOOL BUS STOP AHEAD			1				X												THINNING AND TRIMMING NEEDED			
EB	4.764	A	VW-133L	30	30			6.25								1		X								INSTALL 250 FEET FROM THE PVT ROY DRIVE SIGN IN THE EASTBOUND DIRECTION			T-81
							SHEET TOTALS	12.50	0.00	1	0	0	1	0	0	1		15.0		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
							TOWN DIRECTIONAL TOTALS	228.41	0.0	3	9	9	53	0	0	27		405.0		0		0.0							

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: WINOOSKI-CAMBRIDGE
PROJECT NUMBER: STPG SIGN(55)

FILE NAME: UNDERHILL VT15 EB TSS.xls
PROJECT MANAGER: M. FOISY
DESIGNED BY: G. BARRETT
UNDERHILL EB SHEET 9

PLOT DATE: 6/14/2016
DRAWN BY: G. BARRETT
CHECKED BY: M. FOISY