DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
UNDERHILL VT-15 WB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																				"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
WB	4.940	F	VW-133R	30	30		HIDDEN DRIVE RIGHT						1	X															
		F	VW-133R	30	30			6.25																			T-81
WB	4.921	F	S3-1	36	36	FYG	SCHOOL BUS STOP AHEAD			1				X														
WB	4.640	F	VW-060	30	30		HIDDEN DRIVES						1	X													THINNING AND TRIMMING NEEDED			
		F	VW-060	30	30			6.25																			T-81
WB	4.480	F	W2-2	30	30		MODIFIED LEFT SIDE ROAD						1		X														
		F	VW-092	24	18		UNSAFE TO PASS						1																
		F	W2-2	30	30			6.25								1		X								X		
		F	VW-092	30	24			5.00																			14	
WB	3.972	F	VS3-4	36	36		SCHOOL BUS TURN AROUND						1	X															
		F	S3-2	36	36	FYG		9.00																			19	
WB	3.886	G	VR-017	24	30		LLL 16,000 LBS						1		X												DAUDELIN RD (TH-18)			
		G	W14-2	30	30		NO OUTLET						1														DAUDELIN RD (TH-18) REMOVE SIGN AND RETURN TO TOWN			
		G	VR-017	24	30			5.00								1		X								DAUDELIN RD (TH-18); INSTALL 20 FEET BACK FROM VT ROUTE 15 EDGE OF PAVEMENT			T-70
WB	3.864	F	D3-1	24	6		DAUDELIN RD						1		X												DAUDELIN RD (TH-18)			
							SHEET TOTALS	37.75	0.00	1	0	0	8	0	0	2		30.0		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
							TOWN DIRECTIONAL TOTALS	212.83	0.0	5	5	5	43	0	0	21		315.0		0		0.0							

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **WINOOSKI-CAMBRIDGE**
PROJECT NUMBER: **STPG SIGN(55)**

FILE NAME: **UNDERHILL VT15 WB TSS.xls** PLOT DATE: **6/14/2016**
PROJECT MANAGER: **M. FOISY** DRAWN BY: **G. BARRETT**
DESIGNED BY: **G. BARRETT** CHECKED **M. FOISY**
UNDERHILL WB SHEET 1 SHEET **166** OF **192**