DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
CAMBRIDGE VT-15 WB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
		F	W13-1P	18	18		40 MPH						1															
		F	W1-2R	30	30			6.25																			X	
		F	W13-1P	18	18			2.25																			X	
WB	1.350	F	S3-1	36	36		SCHOOL BUS STOP AHEAD						1		X													
		F	S3-1	36	36	FYG		9.00								2		X									X	
WB	1.281	F	D3-1	30	6		BLANCHARD RD						1		X												BLANCHARD RD (TH-37)			
		E	R1-1	30	30		STOP						1														BLANCHARD RD (TH-37)			
		F	VD-700	6	10		MILE MARKER 0130				1		1														BLANCHARD RD (TH-37)			
		F	D3-1	42	12		Blanchard Rd	3.50								1		X									BLANCHARD RD (TH-37)		12	
		G	D3-1	42	12		VT Route 15	3.50																			BLANCHARD RD (TH-37)		12	
		H	R1-1	30	30		STOP	6.25																			BLANCHARD RD (TH-37)			
		G	VD-700	6	10		0150 0802 0130					1															BLANCHARD RD (TH-37)			
WB	1.276	F	VR-017	24	30		LLL 24,000						1		X												BLANCHARD RD (TH-37) REMOVE SIGN AND RETURN TO TOWN			
		F	W14-1	30	30		DEAD END						1														BLANCHARD RD (TH-37) REMOVE SIGN AND RETURN TO TOWN			
WB	1.190	F	VD-062B	72	16		BUSINESS SIGN- BUSINESS PARK AT CAMBRIDGE			1				X																
							SHEET TOTALS	30.75	0.00	1	1	1	7	0	0	3		45.0		0	0.0	0.0	0.0	0.0				
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB				
							TOWN DIRECTIONAL TOTALS	226.41	0.0	3	3	3	54	0	0	19		285.0		0		0.0						

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: WINOOSKI-CAMBRIDGE
PROJECT NUMBER: STPG SIGN(55)
FILE NAME: CAMBRIDGE VT15 WB TSS.xls PLOT DATE: 6/14/2016
PROJECT MANAGER: M. FOISY DRAWN BY: G. BARRETT
DESIGNED BY: G. BARRETT CHECKED M. FOISY
CAMBRIDGE WB SHEET 6 SHEET 189 OF 192