



### THINNING AND TRIMMING FOR SIGNS DETAIL

2-1/2" SOIL BEARING SLIP BASE LOCATIONS				
ROUTE	TOWN	MILE POINT	DESCRIPTION	QTY.
VT5A	BURKE	0.066	BRK HLLW/ E. BRK/ JCT5/ END 5A	2
	BROWNINGTON	0.606	EVAN/ ORL./W. CHLST./I POND	2
	CHARLESTON	3.792	W CHL./D CTR/E CHL./I POND	2
VT114	LYNDON	0.115	WHLK/ LYNDV/ W BURKE	2
	LYNDON	0.209	JCT 122/ JCT 5/ END 114	2

LOCATIONS				
ROUTE	TOWN	MILE POINT	DESCRIPTION	
US 5	LYNDON	6.550	SIDE ROAD WARN. / CALENDAR BRK RD	
	BURKE	0.526	SCHOOL BUS TURN AROUND	
	SUTTON	0.164	SPEED LIMIT 35 AHEAD	
	SUTTON	0.368	BUSINESS INFORMATION	
	SUTTON	0.680	CURVE LEFT	
	SUTTON	2.049	MICHAUD DR	
	SUTTON	2.519	US ROUTE 5 / PIERCE HILL RD	
	DERBY	5.855	PEDESTRIAN / 45 DEG. ARROW	
	VT 5A	BURKE	0.405	NORTH RIDGE RD
		SUTTON	1.023	BENTON DR
WESTMORE		0.000	US ROUTE 5 / ACADIA LN	
WESTMORE		0.012	WILLOUGHBY RIDGE	
WESTMORE		0.234	MOOSE CROSSING	
WESTMORE		1.556	SPEED LIMIT 35 / MAY 15 TO SEPT 15	
WESTMORE		1.960	SUMMER CAMP AREA	
VT 114	BROWNINGTON	0.644	ROUTE MARKER ASSEMBLY	
	LYNDON	2.984	MT HUNGER RD/EAST BURKE RD	
	BURKE	4.950	SCHOOL BUS STOP AHEAD	

**NOTE:**

THE CONTRACTOR SHALL REMOVE ALL WOODY STEMMED GROWTH INCLUDING BRUSH, SAPLINGS, TREES AND TREE LIMBS GROWING WITHIN OR PROJECTING INTO THE CLEARANCE AREA AND DOWN TO GROUND LEVEL OR AT LEAST 10 FT BELOW THE BOTTOM OF THE SIGN. THIS WORK WILL BE PERFORMED AT THE DIRECTION OF THE ENGINEER AND PAID FOR UNDER CONTRACT ITEM 201.31 "THINNING AND TRIMMING FOR SIGNS" AND PAID FOR PER EACH. THIS WORK SHALL BE DONE AT THE SAME TIME THE SIGN IS INSTALLED, OR AS DIRECTED BY THE ENGINEER. NO CHEMICALS (POISONS OR DEFOLIANTS) ALLOWED.

**MINIMUM SIGN SIGHT DISTANCE CHART**

APPROACH SPEED (mph)	SIGHT DISTANCE (feet)
30 OR LESS	300
35	350
40	400
45	450
50	500
55	550

PROJECT NAME:	STATEWIDE-NORTHEAST
PROJECT NUMBER:	STPG SIGN (56)
FILE NAME:	z15T007det.dgn
PROJECT LEADER:	B. BRESLEND
DESIGNED BY:	J. GOODALL
DETAIL SHEET	2
PLOT DATE:	5/4/2016
DRAWN BY:	O. DALMER
CHECKED BY:	C. LATHROP
SHEET	5 OF 168