DIR	MILEPOINT	LOCATION CODE	MUTCD CODE	WIDTH	HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (in) 1.75 (LB / FT) 1.88	SQUARE STEEL (in) 2.00 (LB / FT) 2.42	SQUARE STEEL (in) 2.50 (LB / FT) 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHSM	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
SUTTON			**US5**	**SB**			FYG-FLUORESCENT YELLOW-GREEN																			"SHSM" - STANDARD HIGHWAY SIGNS AND MARKINGS			
		G	UNK.	18	24		NO ATV'S ALLOWED				1	1	1			1		15'-3" X								SALVAGE SIGN ON NEW POST IN EXISTING LOCATION			
		G	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS	5.00																				T-70
SB	6.365	G	VD3-1	54	12		US ROUTE 5						1		1													
		F	VD3-1	66	12		UNDERPASS RD						1															
SB	6.375	F	VD3-1	66	12		Underpass Rd	5.50								2		13'-0" X 13'-0"								INSTALL SIGN BETWEEN STOP SIGN AND INTERSECTION		16	
SB	6.371	H	R1-1	30	30		STOP						1		1													
		H	R1-1	30	30		STOP MOUNTED STOP SIGN TO UNDERPASS RD. STREET SIGN	6.25								1		~~X~~									X		
SB	6.313	F	R2-1	24	30		SPEED LIMIT 50						1		1													
		F	R2-1	24	30		SPEED LIMIT 50	5.00								1		13'-9" X									X		
SB	4.550	F	R2-1	24	30		SPEED LIMIT 50	5.00								1		15'-9" X								INSTALL SIGN 620 FEET SOUTH OF DOLLOFF POND ROAD	X		
SB	3.639	F	VD-701	6	8		BRIDGE 151 VT US 5			1				1														
SB	2.171	G	VR-017	24	30		LLL 24,000 LBS						1		1													
		G	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS	5.00								1		13'-3" X											T-70
SB	2.171	A	VD3-1	48	12		Station Rd	4.00								2		11'-3" X 11'-6"								INSTALL SIGN IN FRONT OF "LEGAL LOAD LIMIT 24,000 LBS " SIGN		16	
SB	2.162	H	R1-1	30	30		STOP						1		1													
							SHEET TOTALS	35.75 SF	0.00 SF	1 EA	1 EA	1 EA	7 EA	1 EA	5 EA	9 EA		135 FT											
							TOWN TOTALS	103.83	0.0	6.0	2.0	2.0	20.0	9.0	13.0	18		270.0											

10/17/16

10/5/16

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **STATEWIDE- NORTHEAST**
PROJECT NUMBER: **STPG SIGN(56)**

FILE NAME: **z15T007 US5-SUTTON-SB.xls**
PROJECT MANAGER: **B. BRESLEND**
DESIGNED BY: **O. DALMER**
SUTTON US5 SB 2

PLOT DATE: **5/4/2016**
DRAWN BY: **O. DALMER**
CHECKED BY: **B. BRESLEND**