	DIR	MILEPOINT	LOCATION CODE	MUTCD CODE	WIDTH	HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (in) 1.75 (LB / FT) 1.88	SQUARE STEEL (in) 2.00 (LB / FT) 2.42	SQUARE STEEL (in) 2.50 (LB / FT) 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHSM	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
	WESTMORE			**VT5A**	**NB**			FYG-FLUORESCENT YELLOW-GREEN																			"SHSM" - STANDARD HIGHWAY SIGNS AND MARKINGS			
10/18/16	NB	0.000	C	VD-024	72	10		WESTMORE / NEWARK						1		1													
			C	VD-025	72	10		ORLEANS CO / CALEDONIA CO						1															
			C	VD-024	72	10		Westmore / Newark	5.00								2		13'-6" X 14'-0"										T-94
			C	VD-025	72	10		Orleans Co / Caledonia Co; 0051 1019 0000; 0051 0308 0085	5.00																				T-94
			C	VD-700	6	10			0.42																				T-44
			C	VD-700	6	10			0.42																				T-44
	NB	0.000	C	VD3-1	54	12		VT RTE 5A			1				1												REQUIRES VEGETATION CLEARING			
			C	VD3-1	48	12		ARCADIA LN			1																			
	NB	0.000	C	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS	5.00					1			1		13'-9" X								INSTALL SIGN ON SOUTH SIDE OF ROAD , BEHIND "TOWN/COUNTY LINE" SIGN ASSEMBLY			T-70
	NB	0.005	D	R1-1	30	30		STOP	6.25								1		13'-3" X								INSTALL SIGN ON NORTH SIDE OF ROAD	X		
10/19/16	NB	0.234	A	VW-000	30	30		MOOSE CROSSING						1		1													
			A	VW-000	30	30		MOOSE CROSSING	6.25								1		15'-0" X								REQUIRES VEGETATION CLEARING			T-80
	NB	0.915	A	W11-2	30	30		PEDESTRIAN						1		1													
			A	W11-2	30	30	FYG		6.25								1		15'-3" X									X		
			A	W16-4P	24	18	FYG	NEXT 900 FT	3.00																			X		
								SHEET TOTALS	37.59 SF	0.00 SF	2 EA	0 EA	0 EA	4 EA	1 EA	3 EA	6 EA		90 FT										
								TOWN TOTALS	310.66 SF	0.0 SF	24.0 EA	1.0 EA	1.0 EA	61.0 EA	32.0 EA	39.0 EA	39 EA		585.0 FT										

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **STATEWIDE- NORTHEAST**
PROJECT NUMBER: **STPG SIGN(56)**

FILE NAME: **z15T007VT5A-WESTMORE-NB** PLOT DATE: **5/4/2016**
PROJECT MANAGER: **B. BRESLEND** DRAWN BY: **O. DALMER**
DESIGNED BY: **O. DALMER** CHECKED BY: **B. BRESLEND**
WESTMORE VT5A NB 1 SHEET **76** OF **168**