| | DIR | MILEPOINT | LOCATION CODE | MUTCD CODE | WIDTH | HEIGHT | SHEETING REMARKS | SIGN LEGEND | NEW SIGNS "A" | NEW SIGNS "B" | EXISTING SIGNS RETAIN | EXISTING SIGNS SALVAGE FROM | EXISTING SIGNS SALVAGE TO | EXISTING SIGNS REMOVE | EXIST POST RETAIN | EXIST POST REMOVE | NUMBER OF NEW POSTS | SQUARE STEEL (in) 1.75 (LB / FT) 1.88 | SQUARE STEEL (in) 2.00 (LB / FT) 2.42 | SQUARE STEEL (in) 2.50 (LB / FT) 3.35 | FOUNDATION | TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60 | TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00 | TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80 | TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60 | SIGN FRAME REQUIRED | REMARKS | SIGN DETAIL: DETAIL IN SHSM | SIGN DETAIL: DETAIL ON SHEET NUMBER | SIGN DETAIL: DETAIL ON STD SHEET NUMBER |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | **CHARLESTON** | | | | **VT5A** | | **SB** | FYG-FLUORESCENT YELLOW-GREEN | | | | | | | | | | | | | | | | | | | "SHSM" - STANDARD HIGHWAY SIGNS AND MARKINGS | | | |
| | SB | 3.817 | F | M3-3 | 24 | 12 | | SOUTH | | | | | | 1 | | 1 | | | | | | | | | | | | | |
| | | | F | VM1-5 | 24 | 24 | | VT 5A | | | | | | 1 | | | | | | | | | | | | | | | |
| | | | F | UNK. | 12 | 24 | | NEK | | | | 1 | 1 | 1 | | | | | | | | | | | | | SALVAGE SIGN ON NEW POST IN EXISTING LOCATION | | | |
| | | | F | M3-3 | 24 | 12 | | SOUTH | 2.00 | | | | | | | | 1 | | 15'-6" X | | | | | | | | GREEN ON WHITE | X | | |
| | | | F | VM1-5 | 24 | 24 | | VERMONT 5A | 4.00 | | | | | | | | | | | | | | | | | | | | E-136B |
| | SB | 3.773 | F | VD2-1 | 72 | 12 | | LAKE WILLOUGHBY 9 | | | | | | 1 | | 2 | | | | | | | | | | | | | |
| 11/7/16 | | | F | VD2-1 | 72 | 12 | | WEST BURKE 21 | | | | | | 1 | | | | | | | | | | | | | | | |
| | | | F | VD2-1 | 72 | 12 | | Willoughby Lake 9 | 6.00 | | | | | | | | 2 | | 13'-0" X 14'-6" | | | | | | | | | | 9 | |
| | | | F | VD2-1 | 72 | 12 | | West Burke 21 | 6.00 | | | | | | | | | | | | | | | | | | | | 9 | |
| | SB | 3.676 | E | W3-1 | 36 | 36 | | STOP AHEAD | | | | | | 1 | | 2 | | | | | | | | | | | | | |
| | | | E | W3-1 | 30 | 30 | | | 6.25 | | | | | | | | 1 | | 15'-9" X | | | | | | | | | X | | |
| | SB | 2.512 | F | W11-6H | 30 | 30 | | SNOWMOBILE | | | | | | ~~1~~ | | 1 | | | | | | | | | | | | | |
| | SB | 2.476 | F | W11-6H | 30 | 30 | | | 6.25 | | | | | | | | 1 | | X | | | | | | | | INSTALL SIGN IN CLOSED POSITION 90 FEET SOUTH OF CURRENT LOCATION | | 14 | |
| 11/4/16 | SB | 1.260 | F | VD3-1 | 66 | 12 | | BATCHELDER RD | | | 1 | | | | 1 | | | | | | | | | | | | | | | |
| | SB | 0.881 | F | VD1-1A | 72 | 10 | | <--- EAST CHARLESTON 7 | | | | | | 1 | 2 | | | | | | | | | | | | | | | |
| | | | | | | | | SHEET TOTALS | 30.50 SF | 0.00 SF | 1 EA | 1 EA | 1 EA | 8 EA | 3 EA | 6 EA | 5 EA | 75 FT | | | | | | | | | | | |
| | | | | | | | | TOWN TOTALS | 111.50 | 0.0 | 3.0 | 2.0 | 2.0 | 20.0 | 9.0 | 11.0 | 15 | 225.0 | | | | | | | | | | | |

## SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **STATEWIDE- NORTHEAST**
PROJECT NUMBER: **STPG SIGN(56)**
FILE NAME: **z15T007VT5A-CHARLESTON-S** PLOT DATE: **5/4/2016**
PROJECT MANAGER: **B. BRESLEND** DRAWN BY: **O. DALMER**
DESIGNED BY: **O. DALMER** CHECKED BY: **B. BRESLEND**
CHARLESTON VT5A SB 2 SHEET **112** OF **168**