	DIR	MILEPOINT	LOCATION CODE	MUTCD CODE	WIDTH	HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (in) 1.75 (LB / FT) 1.88	SQUARE STEEL (in) 2.00 (LB / FT) 2.42	SQUARE STEEL (in) 2.50 (LB / FT) 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHSM	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
	BURKE			**VT114**	**SB**			FYG-FLUORESCENT YELLOW-GREEN																			"SHSM" - STANDARD HIGHWAY SIGNS AND MARKINGS			
11/2/16	SB	0.377	G	VD3-1	24	6		VT ROUTE 114						1		1													
			F	VD3-1	36	6		BURKE HOLLLOW RD						1															
			G	VD3-1	60	12		VT Route 114	5.00								3		11'-0" X 11'-0" 12'-9"										18	
			F	VD3-1	72	12		Burke Hollow Rd	6.00																				17	
11/1/16	SB	0.377	G	R1-2	36	36		YIELD						1		1													
			G	R1-2	36	36		YIELD	4.50								~~2~~ 1		13'-3" X									X		
	SB	0.366	H	R1-1	30	30		STOP						1		1													
			H	R1-1	30	30		STOP	6.25								1		13'-3" X									X		
	SB	0.349	F	UNK.	12	18		NEK (NORTHEST KINGDOM BYWAY)			1				1														
	SB	0.232	F	R2-1	24	30		SPEED LIMIT 40						1		1													
			F	R2-1	24	30		SPEED LIMIT 40	5.00								1		14'-3" X									X		
11/2/16	SB	0.042	F	W11-6H	30	30		HINGED SNOWMOLBILE						1		1													
			F	W11-6H	30	30			6.25								1		15'-0" X								INSTALL SIGN IN CLOSED POSITION		14	
	SB	0.001	F	R2-1	24	30		SPEED LIMIT 50						1		1													
			F	R2-1	24	30		SPEED LIMIT 50	5.00								1		13'-3" X									X		
								SHEET TOTALS	38.00	0.00	1	0	0	7	1	6	9		135											
									SF	SF	EA	EA	EA	EA	EA	EA	EA		FT											
								TOWN TOTALS	266.00	0.0	8.0	1.0	1.0	50.0	10.0	42.0	51		765.0											

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: STATEWIDE- NORTHEAST
PROJECT NUMBER: STPG SIGN(56)

FILE NAME: z15T007VT114-BURKE-SB.xls
PROJECT MANAGER: B. BRESLEND
DESIGNED BY: O. DALMER
BURKE VT114 SB 7

PLOT DATE: 5/4/2016
DRAWN BY: O. DALMER
CHECKED BY: B. BRESLEND
SHEET 143 OF 168