


PROJECT # 12117067

PO # 6195

DATASHEET 

Autoscope ENCORE Access Point (TAP)



The Autoscope ENCORE Access Point is a robust Autoscope Detector Port Master (DPM) with EasyLink connectivity for up to eight Autoscoptes

About Access Point

The *Autoscope* ENCORE Access Point is a robust *Autoscope* Detector Port Master (DPM) with EasyLink connectivity for up to eight *Autoscope* devices. The *Access Point* outputs vehicle detection events to the traffic controller. A well-organized user-selectable video output simplifies maintenance and monitoring. Its video switch provides standard National Television Standards Committee (NTSC) or Phase Alternating Line (PAL) analog video for access in the traffic cabinet.

EasyLink connectivity means simple installation within the cabinet for I/O recognition to the traffic controller. The *Autoscope* Configuration Wizard[®] promptly associates the TAP with other *Autoscope* devices. Point-and-click I/O assignments quickly configure the interface to the traffic controller.

At A Glance

- Rack or stand-alone installation
- Self-diagnostics on power-up
- High-energy transient protection
- Supports up to 8 *Autoscope* devices
- EasyLink IP-addressable connectivity
- 88 total simultaneous outputs
- 48 total simultaneous inputs
- 64 TS2 detector outputs

