

QUANTITY SHEET

SUMMARY OF ESTIMATED QUANTITIES													TOTALS			DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
													ROADWAY	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
													1350	1350		HR	TRUCK-MOUNTED ATTENUATOR, AWW/PV	608.50	EST.			
													725	725		HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST.			
													1	1		LS	MOBILIZATION/DEMOBILIZATION	635.11	--			
													1	1		LS	TRAFFIC CONTROL	641.10	--			
													9389000	9389000		LF	4 INCH WHITE LINE, WATERBORNE PAINT (FPQ)	646.201	FPQ			
													8408000	8408000		LF	4 INCH YELLOW LINE, WATERBORNE PAINT (FPQ)	646.2111	FPQ			
													550000	550000		LF	6 INCH WHITE LINE, WATERBORNE PAINT	646.2141	EST.			
													463000	463000		LF	6 INCH YELLOW LINE, WATERBORNE PAINT	646.2151	EST.			
													9500	9500		LF	8 INCH WHITE LINE, WATERBORNE PAINT	646.221	EST.			
													23050	23050		LF	8 INCH YELLOW LINE, WATERBORNE PAINT	646.231	EST.			
													11850	11850		LF	12 INCH WHITE LINE, WATERBORNE PAINT	646.241	EST.			
													550	550		LF	12 INCH YELLOW LINE, WATERBORNE PAINT	646.251	EST.			

PROJECT NAME: STATEWIDE SOUTH REGION
PROJECT NUMBER: STPG MARK(305)
FILE NAME: +15+046frm.dgn PLOT DATE: 2/19/2016
PROJECT LEADER: P. COBURN DRAWN BY: K. RECORD
DESIGNED BY: K. RECORD CHECKED BY: I. DEGUTIS
QUANTITY SHEET SHEET 2 OF 11