



### TRUCK APRON DETAIL

NOT TO SCALE

**NOTES:**

1. ALL REINFORCING STEEL SHALL BE EPOXY COATED AND WILL BE PAID FOR UNDER ITEM 507.II REINFORCING STEEL, LEVEL I. THE CONTRACTOR SHALL PROVIDE A REINFORCING SCHEDULE TO THE RESIDENT ENGINEER FOR REVIEW AND APPROVAL PRIOR TO ORDERING ANY MATERIAL. PAYMENT FOR THE REINFORCING SCHEDULE WILL BE CONSIDERED INCIDENTAL TO ITEM 507.II.
2. THE COLOR OF THE CONCRETE AGGREGATE SHALL MATCH THAT OF THE COLOR OF THE CONCRETE.
3. PATTERN SHALL MIMIC RANDOM FIELDSTONE WITH A LIGHT GREY COLOR SIMILAR TO THE PATTERN USED AT THE ROUNDABOUT AT INTERSECTION OF VT15 AND ALT VT100 IN MORRISTOWN.
4. CONCRETE FOR THE TRUCK APRON WILL BE PAID FOR UNDER ITEM 900.675 - SPECIAL PROVISION (STAMPED CONCRETE ISLAND, 8")
5. THE SURFACE OF THE GRADED CRUSHED STONE SHALL BE ROUGHENED DURING PREPARATION OF THE APRON INSTALLATION. PAYMENT WILL BE CONSIDERED INCIDENTAL TO ITEM 900.675 - SPECIAL PROVISION (STAMPED CONCRETE ISLAND, 8")
6. 3" SAWN JOINTS IN TRUCK APRON WILL BE CONSIDERED INCIDENTAL TO ITEM 900.675 - SPECIAL PROVISION (STAMPED CONCRETE ISLAND, 8")

PROJECT NAME: MORRISTOWN  
PROJECT NUMBER: STPG SGNL(47)

FILE NAME: z15+047det.dgn  
PROJECT LEADER: J. SANTACRUCE  
DESIGNED BY: R. LUCHINI  
DETAIL SHEET

PLOT DATE: 5/17/2016  
DRAWN BY: R. LUCHINI  
CHECKED BY: B. COLBURN  
SHEET 7 OF 58

