

QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
								ROADWAY	EROSION CONTROL	FULL C.E.	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
								805			805		CY	COMMON EXCAVATION	203.15	2			
								15			15		CY	EXCAVATION OF SURFACES AND PAVEMENTS	203.28	0.3			
								155			155		CY	EARTH BORROW	203.30	0.3			
								340			340		CY	SAND BORROW	203.31	19.6			
								10			10		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	EST			
								3250			3250		SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10	14.7			
								620			620		CY	SUBBASE OF DENSE GRADED CRUSHED STONE	301.35	61.7			
														BEGIN OPTION AA					
								55			55		TON	AGGREGATE SHOULDERS	402.12	3.1			
								55			55		TON	AGGREGATE SHOULDERS, RAP	402.13	3.1			
														END OPTION AA					
								1			1		LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50	-			
								4			4		CY	CONCRETE, HIGH PERFORMANCE CLASS B	501.34	1.03			
								3800			3800		LB	REINFORCING STEEL, LEVEL I	507.11	76			
								2			2		GAL	WATER REPELLENT, SILANE	514.10	1			
								12			12		LF	8 INCH UNDERDRAIN CARRIER PIPE	605.21	1			
								2			2		TON	BITUMINOUS CONCRETE SIDEWALK	618.15	0.4			
								87			87		LF	CHAIN-LINK FENCE, 4 FEET (VINYL COATED - BLACK)(PAINT POSTS - BLACK)	620.11	0.4			
								4			4		EACH	BRACING ASSEMBLY FOR CHAIN-LINK FENCE, 4 FEET (PAINT - BLACK)	620.20	-			
								93			93		LF	REMOVAL OF EXISTING FENCE	620.55	-			
								50			50		LF	STEEL BEAM GUARDRAIL, GALVANIZED	621.20	EST			
								3			3		EACH	ENERGY ABSORPTION ATTENUATOR	621.56	-			
								505			505		LF	REMOVE AND RESET GUARDRAIL	621.75	3.2			
								470			470		LF	TEMPORARY TRAFFIC BARRIER	621.90	3			
								480			480		HR	UNIFORMED TRAFFIC OFFICERS	630.10	-			
								800			800		HR	FLAGGERS	630.15	-			
										1	1		LS	FIELD OFFICE, ENGINEERS	631.10	-			
										1	1		LS	TESTING EQUIPMENT, CONCRETE	631.16	-			
										1	1		LS	TESTING EQUIPMENT, BITUMINOUS	631.17	-			
										3000	3000		DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26	-			
								1			1		LS	MOBILIZATION/DEMOBILIZATION	635.11	-			
								1			1		LS	TRAFFIC CONTROL	641.10	-			
								3			3		EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	-			
								2750			2750		LF	DURABLE 4 INCH WHITE LINE, RECESSED POLYUREA	646.406	60			
								1700			1700		LF	DURABLE 4 INCH YELLOW LINE, RECESSED POLYUREA	646.416	24			
								82			82		LF	DURABLE 24 INCH STOP BAR, RECESSED POLYUREA	646.486	-			
								51			51		EACH	DURABLE LETTER OR SYMBOL, RECESSED TYPE C TAPE	646.4973	-			
								1600			1600		LF	TEMPORARY 4 INCH WHITE LINE, PAINT	646.602	126			
								900			900		LF	TEMPORARY 4 INCH YELLOW LINE, PAINT	646.612	64			
								30			30		LF	TEMPORARY 24 INCH STOP BAR, PAINT	646.682	4			

PROJECT NAME: MORRISTOWN
 PROJECT NUMBER: STPG SGNL(47)
 FILE NAME: z15+047qyl.dgn
 PROJECT LEADER: J. SANTACRUCE
 DESIGNED BY: J. SANTACRUCE
 QUANTITY SHEET 1

PLOT DATE: 5/13/2016
 DRAWN BY: J. SANTACRUCE
 CHECKED BY: B. COLBURN
 SHEET 15 OF 58

